

SCHEDULE OF QUANTITIES

FAS ROUTE NO.	SEC	COUNTY	TOTAL SHEETS	SHEET NO
-	*	LEE	20	4

ILLINOIS PROJECT TE-D2(115)

* 01-P4000-00-BT

20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
LOCATION		UNITS
LT. STA. 109+34		14
	TOTAL	14
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	
LOCATION		UNITS
RT. STA. 109+71		30
RT. STA. 110+04		16
RT. STA. 110+04		16
RT. STA. 110+04		16
RT. STA. 110+04		16
	TOTAL	94
25000800	SEEDING, CLASS 1, SPECIAL	
LOCATION		ACRES
LT. STA. 100+00 - LT. STA. 107+15.1		0.0375
RT. STA. 100+00 - RT. STA. 107+15.1		0.0349
LT. STA. 108+62.5 - LT. STA. 111+60.7		0.0456
RT. STA. 108+62.5 - RT. STA. 111+60.7		0.0582
	TOTAL	0.1761
28000400	PERIMETER EROSION BARRIER	
LOCATION		FOOT
RT. STA. 105+00 - RT. STA. 106+00		99
LT. STA. 105+49 - LT. STA. 107+15		168
RT. STA. 109+22 - RT. STA. 110+67		150
LT. STA. 108+31 - LT. STA. 109+60		160
	TOTAL	587
28100109	STONE RIPRAP, CLASS A6	
LOCATION		SQ. YD.
RT. STA. 106+00 - RT. STA. 106+98		99
RT. STA. 108+35 - RT. STA. 108+78		24
	TOTAL	123
28200100	FILTER FABRIC FOR USE WITH RIPRAP	
LOCATION		SQ. YD.
RT. STA. 106+00 - RT. STA. 106+98		99
RT. STA. 108+35 - RT. STA. 108+78		24
	TOTAL	123

35101400	AGGREGATE BASE COURSE, TYPE B	
LOCATION		TON
STA. 100+00 - STA. 106+88.81		459
LT. STA. 103+38		22
STA. 109+16.5 - STA. 111+60.74		163
	TOTAL	644
40200800	AGGREGATE SURFACE COURSE, TYPE B	
LOCATION		TON
UNDER PEORIA AVE. BRIDGE		225
	TOTAL	225
40500100	BITUMINOUS MATERIALS (PRIME COAT)	
LOCATION		GALLON
STA. 100+00 - STA. 106+88.81		322
LT. STA. 103+38		16
STA. 109+16.5 - STA. 111+60.74		114
	TOTAL	452
40500300	BITUMINOUS MIXTURE COMPLETE	
LOCATION		TON
STA. 100+00 - STA. 106+88.81		106
LT. STA. 103+38		1
	TOTAL	107
51204900	STEEL SHEET PILING	
LOCATION		SQ. FT.
RT. STA. 106+91 - RT. STA. 107+15		220
	TOTAL	220
81012600	CONDUIT IN TRENCH, 2" DIA. PVC	
LOCATION		FOOT
LT. STA. 109+10 - LT. STA. 109+25		14
LT. STA. 109+25 - LT. STA. 110+00		76
LT. STA. 110+00 - LT. STA. 110+80		78
	TOTAL	168
81400100	HANDHOLE	
LOCATION		EACH
LT. STA. 109+10		1
	TOTAL	1
	LIGHT POLE FOUNDATION, 20" DIAMETER	
LOCATION		EACH
LT. STA. 109+25		1
LT. STA. 110+00		1
LT. STA. 110+80		1
	TOTAL	3
A2001714	TREE ACER SACCHARUM (SUGAR MAPLE) 1 3/4" CALIPER, BALLED & BURLAPPED	
LOCATION		EACH
JOBSITE		8
	TOTAL	8

A2007114	TREE QUERCUS RUBRA (RED OAK) 1 3/4" CALIPER, BALLED & BURLAPPED	
LOCATION		EACH
JOBSITE		8
	TOTAL	8
B2005064	TREE MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE) 5' HEIGHT, CLUMB FORM, BALLED & BURLAPPED	
LOCATION		EACH
JOBSITE		8
	TOTAL	8
	BRICK SURFACE COURSE	
LOCATION		S.Y.
STA. 109+16.5 - STA. 111+60.74		272
	TOTAL	272
X0322973	REMOVE EXISTING SEA WALL	
LOCATION		FOOT
RT. STA. 108+35 TO RT. STA. 109+16		81
	TOTAL	81
63400305	GUARD POST, SPECIAL	
LOCATION		EACH
STA. 100+05		2
	TOTAL	2

SIGN SCHEDULE					
LOCATION	METAL POST TYPE A	M.U.T.C.D. CODE			DISMOUNT YOUR BIKE
		R1-1 1.13 SQ FT	D11-1 3.0 SQ FT	M7-1 0.75 SQ FT	
STA. 100+00	2 @ 10, 1 @ 12	1	2	1	
STA. 110+00	2 @ 10		2		
RT. STA. 114+20	1 @ 12				1
	64 FEET	2.26 SQ FT	12.0 SQ FT	0.75 SQ FT	1.5 SQ FT
					16.51 SQ FT

EARTH WORK SCHEDULE		
LOCATION	EARTH EXCAVATION	EMBANKMENT
	CU. YD.	CU. YD.
STA. 100+00 - STA. 106+88	376	44
STA. 108+62 - STA. 111+51	506	17
	TOTAL	61

© WENDLER ENGINEERING SERVICES, INC. 2004

WENDLER ENGINEERING SERVICES, INC.
Structural & Civil Engineers—Land Surveying—Environmental Services
Illinois Professional Design Firm No. 184-000848



698 TIMBER CREEK ROAD - P.O. BOX 486 - DIXON, IL 61021 - 815-288-2261
28 E. MARION - SUITE 3 - PRINCETON, IL 61356 - 815-879-4731
1770 WEST STATE ST. - SYCAMORE, IL 60178 - 815-895-5008
804 FREEPORT RD. - STERLING, IL 61081 - (815) 626-4428
E-MAIL: info@wendler.nu

SCALE: 1"=10'

REVISION	DATE	SUPERVISED BY	JOB NO.	DRAWN BY	DESIGNED BY
			99022	BDS	
			SCHD	2/3/2004	
TITLE: SCHEDULE OF QUANTITIES					
CLIENT: DIXON PARK DISTRICT					