

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	38-1RS	MCDONOUGH	83	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ITEM	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	TEMPORARY SEEDING*	GRADING & SHAPING DITCHES	AGGREGATE DITCH CHECK
LOCATION	ACRE	POUND	POUND	POUND	ACRE	ACRE	FT	EA
NB								
STA 115+50 - 117+50	0.02	1.65	1.65	1.65	0.02	0.04	200	2
STA 125+00 - 126+00	0.01	0.83	0.83	0.83	0.01	0.02	100	
STA 143+00 - 147+00	0.04	3.31	3.31	3.31	0.04	0.07	400	3
STA 153+00 - 156+00	0.03	2.48	2.48	2.48	0.03	0.06	300	2
STA 175+75 - 179+00	0.03	2.69	2.69	2.69	0.03	0.06	325	4
STA 181+10 - 188+00	0.06	5.70	5.70	5.70	0.06	0.13	690	6
STA 216+00 - 224+00	0.07	6.61	6.61	6.61	0.07	0.15	800	7
STA 237+00 - 239+50	0.02	2.07	2.07	2.07	0.02	0.05	250	22
SB								
STA 127+30 - 138+00	0.10	8.84	8.84	8.84	0.10	0.20	1070	10
STA 138+00 - 150+00	0.11	9.92	9.92	9.92	0.11	0.22	1200	11
STA 173+00 - 180+00	0.06	5.79	5.79	5.79	0.06	0.13	700	6
STA 181+00 - 211+82	0.28	25.47	25.47	25.47	0.28	0.57	3082	29
TOTAL	0.84	75.60	75.60	75.60	0.84	1.67	9117	102

*2 Applications

INLET & PIPE PROTECTION	
LOCATION	EACH
46' LT STA 126+00	1
54' RT STA 150+00	1
137' RT STA 180+19	1
44' LT STA 181+00	1
63' RT STA 181+07	1
50' LT STA 223+90	1
50' LT STA 239+44	1
TOTAL	7

MOWING	
LOCATION	UNIT
PROJECT LIMITS	192.3
TOTAL	192.3

FILTER FABRIC FOR USE WITH RIPRAP	
NEW GUARDRAIL LOCATIONS	SQ YD
SB RT STA 101+56.07 - 102+06.07	12.1
SB RT STA 106+79.32 - 107+16.82	9
SB RT STA 152+25.45 - 152+75.45	12.1
SB RT STA 155+08.45 - 156+20.95	27.1
SB LT STA 151+72.95 - 152+22.95	12.1
SB LT STA 154+05.95 - 155+18.45	27.1
NB RT STA 156+90.20 - 158+65.20	42.2
NB LT STA 103+82.02 - 104+19.52	9
NB LT STA 109+55.27 - 110+17.77	15.1
NB LT STA 151+84.20 - 152+21.70	9
NB LT STA 155+63.20 - 157+63.20	48.2
RIPRAP LOCATIONS	
RT STA 105+00	55.2
TOTAL	278.2

STONE DUMPED RIPRAP, CLASS A5	
LOCATION	TON
RT STA 153+83.5 - 154+70.5	73.6
TOTAL	73.6

STONE DUMPED RIPRAP, CLASS B3	
LOCATION	TON
RT STA 179+49 - 179+82	19.4
TOTAL	19.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DRAWN BY
CHECKED BY