

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	338-DRS	MCDONOUGH	83	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS RESURFACING

LOCATION	AREA	BIT SURF REMOVAL (4 1/2")	BCSC SUPERPAVE MIX D, N50 (2")	BCBC SUPERPAVE IL 19.0, N50 (2.5")
	SQ FT	SQ YD	TON	TON
CROSSOVERS				
STA 126+60	2941.0	326.8	36.6	45.7
STA 151+30	3066.6	340.7	38.2	47.7
STA 164+80	3036.3	337.4	37.8	47.2
STA 180+20	3316.8	368.5	41.3	51.6
STA 212+10	3016.5	335.2	37.5	46.9
STA 233+75	1941.8	215.8	24.2	30.2
STA 250+85	3055.4	339.5	38.0	47.5
STA 269+30	3100.0	344.4	38.6	48.2
STA 287+35	2132.3	236.9	26.5	33.2
SUB-TOTALS		2845.2	318.7	398.3
TURN LANES				
SB 121+59.40 - 127+50	4998.1	555.3	62.2	77.7
NB 125+35 - 131+99.87	6144.8	682.8	76.5	95.6
SB 146+31.11 - 152+90	6038.6	670.9	75.1	93.9
NB 150+20 - 156+16.80	5093.6	566.0	63.4	79.2
SB 175+19.99 - 181+10	5353.2	594.8	66.6	83.3
NB 179+00.51 - 185+61.51	5905.6	656.2	73.5	91.9
SB 226+99.20 - 235+20	7042.7	782.5	87.6	109.6
SB 228+22.51 - 234+60	6488.3	720.9	80.7	100.9
NB 232+34.10 - 241+13.31	8022.2	891.4	99.8	124.8
NB 237+98.5 - 238+58.58	5372.8	597.0	66.9	83.6
SB 264+22 - 270+00	5197.7	577.5	64.7	80.9
NB 268+60 - 274+09	4825.4	536.2	60.0	75.1
SB 281+91.27 - 289+80	6487.4	720.8	80.7	100.9
SB 282+34.81 - 289+25	4569.1	507.7	56.9	71.1
NB 285+90 - 292+74.26	5946.9	660.8	74.0	92.5
NB 286+45 - 292+35.03	5411.5	601.3	67.3	84.2
MEDIAN 106+21.98 - 117+50	25089.1	2787.7	322.3	402.8
SUB-TOTALS		13109.8	1478.4	1847.9
TOTALS		15955.0	1797.0	2246.2

RESURFACING MAIN LINE ONLY

LOCATION	LENGTH	WIDTH	AREA	BIT SURF REMOVAL BUTT JT	BIT SURF REMOVAL (4 1/2")	POLY BCSC SUPERPAVE MIX D, N50 (2")	POLY BCBC SUPERPAVE IL 19.0, N50 (2.5")
			SQ FT	SQ YD	SQ YD	TON	TON
SOUTH BOUND							
105+64.32 - 106+24.32	60.0	24.0	1440.0	160.0		17.9	22.4
106+24.32 - 152+57.98	4633.7	24.0	111207.8		12356.4	1383.9	1729.9
152+57.98 - 153+17.98	60.0	24.0	1440.0	160.0		17.9	22.4
154+22.56 - 154+82.56	60.0	24.0	1440.0	160.0		17.9	22.4
154+82.56 - 296+70	14187.4	24.0	340498.6		37833.2	4237.3	5296.6
296+70 - 297+30	60.0	24.0	1440.0	160.0		17.9	22.4
NORTH BOUND							
105+59.68 - 106+19.68	60.0	24.0	1440.0	160.0		17.9	22.4
106+19.68 - 152+08.15	4588.5	24.0	110123.3		12235.9	1370.4	1713.0
152+08.15 - 152+68.15	60.0	24.0	1440.0	160.0		17.9	22.4
153+20.11 - 153+80.11	60.0	24.0	1440.0	160.0		17.9	22.4
153+80.11 - 296+70	14289.9	24.0	342957.4		38106.4	4267.9	5334.9
296+70 - 297+30	60.0	24.0	1440.0	160.0		17.9	22.4
MEDIAN 105+61.98 - 106+21.98			806.7	89.6			
TOTALS				1369.6	100531.9	11402.7	14253.6

CONSTRUCTING TEST STRIP

LOCATION	EACH
MAINLINE SURFACE	1
MAINLINE BINDER	1
TURN LANES SURFACE	1
TOTAL	3

MATERIAL TRANSFER DEVICE

LOCATION	TON
MAINLINE SURFACE	11,401.5
MAINLINE BINDER	14,251.9
TOTAL	25,653.4

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DRAWN BY
CHECKED BY