

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(38-1)RS	MCDONOUGH	83	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

BITUMINOUS RESURFACING - SHOULDERS					
LOCATION	AREA	BIT SURF REMOVAL BUTT JT	BIT SURF REMOVAL (4 1/2")	BCSC SUPERPAVE IL 9.5L LE (2")	BCBC SUPERPAVE IL 19.0L LE (2.5")
SHOULDERS	SQ FT	SQ YD	SQ YD	TON	TON
SB - OUTSIDE					
STA 105+65.94 - 106+25.96	594.25	66.0		7.4	9.2
STA 106+25.96 - 125+47.88	19219.5		2135.5	239.2	299.0
STA 127+84.12 - 150+59.41	20517.3		2279.7	255.3	319.2
STA 152+71.20 - 153+29.20	595.1	66.1		7.4	9.3
STA 154+34.66 - 154+94.71	604.6	67.2		7.5	9.4
STA 154+94.71 - 228+23.68	73289.7		8143.3	912.0	1140.1
STA 235+17.11 - 281+93.72	46765.8		5196.2	582.0	727.5
STA 288+83.85 - 296+70	7861.5		873.5	97.8	122.3
STA 296+70 - 297+30	659.8	73.3		8.2	10.3
NB - OUTSIDE					
STA 105+57.67 - 106+18.70	605.3	67.3		7.5	9.4
STA 106+18.70 - 125+84.95	17904.6		1989.4	222.8	278.5
STA 127+74.63 - 151+96.03	14433.7		1603.7	179.6	224.5
STA 151+96.03 - 152+56.15	601.2	66.8		7.5	9.4
STA 153+08.03 - 153+68.08	599.8	66.6		7.5	9.3
STA 153+68 - 179+62.61	25786.5		2865.2	320.9	401.1
STA 181+36.43 - 233+00	49233.0		5470.3	612.7	765.8
STA 234+84.89 - 286+54.77	45029.4		5003.3	560.4	700.5
STA 288+45.69 - 296+70	6034.0		670.4	75.1	93.9
STA 296+70 - 297+30	360.1	40.0		4.5	5.6
SB & NB MEDIAN					
STA 117+47.61 - 126+22.42	12477.4		1386.38	155.3	194.1
STA 126+97.69 - 150+82.11	33476.7		3719.6	416.6	520.7
STA 151+63.53 - 164+54.86	16952.8		1883.6	211.0	263.7
STA 165+05.38 - 179+68.59	19723.2		2191.5	245.4	306.8
STA 180+56.03 - 211+84.26	43919.0		4879.9	546.5	683.2
STA 212+35.52 - 233+24.75	28118.2		3124.2	349.9	437.4
STA 234+15.22 - 250+61.49	21609.8		2401.1	268.9	336.2
STA 251+11.12 - 268+84.67	24231.2		2692.4	301.5	376.9
STA 269+60.46 - 286+90.04	23721.1		2635.7	295.2	369.0
STA 287+76.41 - 296+70	9881.6		1098.0	123.0	153.7
STA 296+70 - 297+30	715.3	79.5		8.9	11.1
TOTALS		592.8	62242.9	7037.6	8796.9

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DRAWN BY
CHECKED BY