

LEVELING BINDER SUMMARY

STA-STA	TOTAL	PLAN	LT	RT	1ST LIFT	
					LT	RT
0-17+19	398.1	398	250	148		
17+19-19+19	107.1	107	28	79		
19+19-26+22	334.8	335	74	261		
26+22-28+92	54.7	55	19	36		
28+92-46+00	342.3	342	180	162	34	
46+00-53+02	138.2	138	71	67		
53+02-61+00	377.3	377	254	123	109	
61+00-68+00	167.9	168	109	59		
68+00-76+21	319.5	320	88	232		
76+21-86+00	236.2	236	135	101		
86+00-96+00	422.4	422	312	110	137	
96+00-96+90	15.8	16	6	10		
TOTAL	2914.3	2914 TONS				

SCHEDULES
BITUMINOUS MATERIALS SCHEDULE

LOCATION	BIT C S.C. SUPER, MIX D	BIT BIND C.S. SUPER	LEVEL BINDER MM SUPER	PRIME
00+00-17+19 LT	177	354	250	315
17+19-19+19 LT	21	41	28	37
19+19-26+22 LT	73	145	74	130
26+22-28+92 LT	28	56	19	50
28+92-46+00 LT	176	352	180	313
46+00-53+02 LT	72	145	71	129
53+02-61+00 LT	83	165	254	147
61+00-68+00 LT	72	144	109	128
68+00-76+21 LT	85	169	88	150
76+21-86+00 LT	101	202	135	180
86+00-96+00 LT	103	206	312	183
96+00-96+90 LT	9	19	6	18
96+90-98+00 LT	11	22	0	20
0+00-17+19 RT	177	354	148	315
17+19-19+19 RT	21	41	79	37
19+19-26+22 RT	73	145	261	130
26+22-28+92 RT	28	56	36	50
28+92-46+00 RT	176	352	162	313
46+00-53+02 RT	72	145	67	129
53+02-61+00 RT	83	165	123	147
61+00-68+00 RT	72	144	59	128
68+00-76+21 RT	85	169	232	150
76+21-86+00 RT	101	202	101	180
86+00-96+00 RT	103	206	110	183
96+00-96+90 RT	9	19	10	18
96+90-98+00 RT	11	22	0	20
TOTAL	2022	4040	2914	3600

01-00093-00-RS
RS-221(104)
CONTRACT 89315

BITUMINOUS MATERIALS RATE OF APPLICATION	
TYPE OF BASE	
BITUMINOUS PRIME	0.08 GAL/SQ YD.
BITUMINOUS MATL	112 LBS/IN/SQ YD.

BITUMINOUS BASE CSE	SCHEDULE VAR. DEPTH
STA 96+00-96+90 LT	115
STA 96+90-98+00 LT	140
STA 96+00-96+90 RT	115
STA 96+90-98+00 RT	140
TOTAL	510

PAINT PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	QUANTITY	
		CENTERLINE YELLOW	EC OR CW WHITE
EBL STA 0+00-47+00	NP	4700'	4700'
EBL STA 47+00-62+00	I	375'	1500'
EBL STA 62+00-98+00	NP	3600'	3600'
WBL STA 0+00-30+00	NP	3000'	3000'
WBL STA 30+00-38+00	I	200'	800'
WBL STA 38+00-56+00	NP	1800'	1800'
WBL STA 62+00-70+80	I	220'	1480'
WBL STA 70+80-98+00	NP	2720'	2720'
CROSSWALK STA 12+35	CW	0	60'
		16615'	19660'
GRAND TOTAL			36275'