

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-10	CHRISTIAN	310	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES					80% FED. 20% STATE TOTAL QUANTITIES		% FEDERAL % STATE CONSTRUCTION AND SAFETY TYPE CODE									
CODE NO.	ITEM	SP. PROV.	UNIT		1000-2A ROADWAY	Y030-1E LIGHTING										
60107600	PIPE UNDERDRAINS 4"		FOOT	77931	77931											
60108100	PIPE UNDERDRAINS 4" (SPECIAL)		FOOT	4406	4406											
60222705	MANHOLES, TYPE A, 5'-DIAMETER, WITH MEDIAN INLET (604101)		EACH	6	6											
60238305	INLETS, TYPE A, WITH MEDIAN INLET (604101)		EACH	1	1											
60246605	MEDIAN INLET (604101)		EACH	7	7											
61100500	EXPLORATION TRENCH 52" DEPTH		FOOT	52800	52800											
61100605	MISCELLANEOUS CONCRETE		CU YD	30	30											
61101013	STORM SEWERS PROTECTED, CLASS A, 12"		FOOT	2000	2000											
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.		EACH	10	10											
61139900	STORM SEWERS, SPECIAL 6"		FOOT	1000	1000											
61140000	STORM SEWERS, SPECIAL 8"		FOOT	1000	1000											
61140100	STORM SEWERS, SPECIAL 10"		FOOT	1000	1000											
61140200	STORM SEWERS, SPECIAL 12"		FOOT	250	250											
61140600	STORM SEWERS, SPECIAL 18"		FOOT	250	250											
63500105	DELINEATORS		EACH	168	168											
64200105	SHOULDER RUMBLE STRIP		FOOT	84016	84016											
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		EACH	122	122											
66700205	PERMANENT SURVEY MARKERS, TYPE I		EACH	5	5											
66700305	PERMANENT SURVEY MARKERS, TYPE II		EACH	4	4											
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	26	26											
67000600	ENGINEER'S FIELD LABORATORY		CAL MO	26	26											
67100100	MOBILIZATION		L SUM	1	1											
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400		L SUM	1	1											
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201		L SUM	1	1											
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM	1	1											
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		L SUM	1	1											

REVISIONS	
NAME	DATE
UNDERDRAINS - SEB	4/19/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 5 OF 9
 FAP 322 (US 51)
 SECTION 11-1
 CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
 DATE 3/21/05 CHECKED BY EBB

4/29/2005 8:51:11 AM C:\Users\jpl\Documents\322\322sumtbl.dwg