

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-10	CHRISTIAN	310	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	% FEDERAL % STATE		CONSTRUCTION AND SAFETY TYPE CODE	
					1000-2A ROADWAY	Y030-1E LIGHTING		
X0324118	GRANULAR CULVERT BACKFILL	•	CU YD	148	148			
* X2020500	EARTH EXCAVATION (ROCKFILL)	•	CU YD	1500	1500			
X2510630	HEAVY DUTY EROSION CONTROL BLANKET		SQ YD	695	695			
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	•	SQ YD	428	428			
X3550510	BITUMINOUS BASE COURSE SUPERPAVE 8½"	•	SQ YD	1387	1387			
X3550815	BITUMINOUS BASE COURSE SUPERPAVE 11¾"	•	SQ YD	2059	2059			
X3560120	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 8 INCH	•	SQ YD	158	158			
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	•	EACH	1	1			
X4023000	TEMPORARY ACCESS (ROAD)	•	EACH	7	7			
X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	•	EACH	19	19			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	•	TON	1177	1177			
X4073066	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9¼"	•	SQ YD	5498	5498			
X4073155	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13¾"	•	SQ YD	123293	123293			
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	•	TON	48	48			
X7015000	CHANGEABLE MESSAGE SIGN	•	CAL MO	56	56			
XX001017	REMOVE RIGHT-OF-WAY MARKERS	•	EACH	3	3			
Z0005000	BITUMINOUS MIXTURE FOR PATCHING POTHoles (COLD MIX)	•	TON	100	100			
Z0007601	BUILDING REMOVAL NO. 1	•	L SUM	1	1			
Z0007602	BUILDING REMOVAL NO. 2	•	L SUM	1	1			
Z0007603	BUILDING REMOVAL NO. 3	•	L SUM	1	1			
Z0007604	BUILDING REMOVAL NO. 4	•	L SUM	1	1			
Z0007605	BUILDING REMOVAL NO. 5	•	L SUM	1	1			
Z0013798	CONSTRUCTION LAYOUT	•	L SUM	1	1			
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	•	CU YD	31.3	31.3			
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	•	EACH	2	2			
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	•	EACH	2	2			

Δ SFTY - 3N
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 8 OF 9
FAP 322 (US 51)
SECTION 11-1
CHRISTIAN COUNTY

SCALE: NONE
DATE: 3/21/05

DRAWN BY: SEB
CHECKED BY: EBB

3/20/2005