92677

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-10	CHRISTIAN	310	23
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIGNAGE SCHEDULE

ROUTE	STATION	LANE	SIDE	FACING	SIGN # MUTCD	SIZE IN X IN W	SIZE IN X IN H	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 3 SQ FT	MESSAGE	# OF POSTS	TELESCOPING STEEL SIGN SUPPORT FOOT	WOOD SIGN SUPPORT FOOT
FAP 322	786+00	NB	OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
			MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
	788+03	NB	MEDIAN	SOUTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	788+52	NB	OUTSIDE	SOUTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	792+10	NB	OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	795+20	NB	OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	795+55		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	796+65		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	797+00	SB	OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	799+00	SB	OUTSIDE	NORTH	R2-1	48	60		20.0		SPEED LIMIT 55	1		17.8
			MEDIAN	NORTH	R2-1	48	60		20.0		SPEED LIMIT 55	1		17.8
	799+00	NB	OUTSIDE	SOUTH	R2-1	48	60		20.0		SPEED LIMIT 65	1		17.8
	799+75	SB	OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	801+75	SB	OUTSIDE	NORTH	W4-2L	48	48		16.0		LT LANE ENDS SYMBOL	2	39.0	
			MEDIAN	NORTH	W4-2L	48	48		16.0		LT LANE ENDS SYMBOL	2	39.0	
	803+00	NB	OUTSIDE	SOUTH	R2-I104	48	96			32.0	SPEED LIMIT TRUCKS OVER 3/8	1		20.8
	803+71	SB	OUTSIDE	NORTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	804+20	SB	MEDIAN	NORTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	806+50	SB	OUTSIDE	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
			MEDIAN	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
	810+50	SB	OUTSIDE	NORTH	W9-2R	48	48		16.0		LANE ENDS MERGE RT	2	39.0	
			MEDIAN	NORTH	W9-2R	48	48		16.0		LANE ENDS MERGE RT	2	39.0	
	814+00	SB	OUTSIDE	NORTH	R2-5a	48	60		20.0		REDUCE SPEED AHEAD	1		21.3
					R2-I101	24	24	4.0			55 MPH			
			MEDIAN	NORTH	R2-5a	48	60		20.0		REDUCE SPEED AHEAD	1		21.3
					R2-I101	24	24	4.0			55 MPH			
	828+00		MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	14.8	
	840+00	NB	OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
			MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.0	
	842+00	NB	MEDIAN	SOUTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	842+48	NB	OUTSIDE	SOUTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	864+20	NB	OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	849+00	NB	OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	849+52		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	850+62		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4	
					R1-2	36		3.9			YIELD			
					R6-1R	36	12	3.0			ONE WAY RT			
	851+00	SB	OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
			MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	16.8	
	853+70	SB	OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
			MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	15.8	
	857+67	SB	OUTSIDE	NORTH	R3-I100R	24	24	4.0			RIGHT TURN LANE	1	18.1	
					M6-2R	21	15	2.2			ARROW RT			
	858+16	SB	MEDIAN	NORTH	R3-I100L	24	24	4.0			LEFT TURN LANE	1	18.1	
					M6-2L	21	15	2.2			ARROW LT			
	860+25	SB	OUTSIDE	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
			MEDIAN	NORTH	W10-2	36	36	9.0			SIDE ROAD W/ RR RT SYMBOL	1	18.0	
	866+75		MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	14.8	
	890+33		MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	14.8	

CONTINNUED ON NEXT SHEET

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SIGNAGE
FAP 322 (US 51)
SECTION 11-1
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
DATE 3/17/05 CHECKED BY EBB

3/29/2005

n:\01files\010329\northplans\022schu01.dgn