


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET
C.H. 12	00-00075-00-PV	MACOUPIN	37	3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ROADWAY SCHEDULE											
LOCATION	BITUMIONUS SURF CSE SUPERPAVE MIX C N50	BITUMIONUS BINDER SUPERPAVE IL-19 N50	BITUMIONUS MATERIALS (PRIME COAT) 0.1 GAL/SY	PROCESSING SOIL CEMENT BASE COURSE 7.5"	CEMENT	AGGREGATE SURFACE COURSE TYPE A	INCIDENTAL BITUMIONUS SURFACING	BITUMIONUS SURFACE REMOVAL BUTT-JOINT	AGGREGATE SURFACE COURSE TYPE B	TEMPORARY RAMP	AGGREGATE SHOULDER TYPE A 6"
	TON	TON	GAL	SQ YD	100WT	TON	TON	SQ YD	TON	SQ YD	SQ YD
CH12											
STA 36+30 TO STA 236+09.04	6046	9974	5356	60219	30784	1700		334		160	26572
UP RR CROSSING APPROACHES	39		28					278		60	
BNSF RR CROSSING APPROACHES	45		35					211		60	
ENTRANCES/MAILBOX TURNOUTS			61				101	91	77.0		24
SIDE ROADS			83				138	126		60	
TOTAL	6130	9974	5563	60219	30784	1700	239	1040	77	340	26596

SEEDING							
LOCATION	CLASS 2 SPECIAL	NITROGEN 90 LBS/ACRE	PHOSPHORUS 90 LBS/ACRE	POTASSIUM 90 LBS/ACRE	AGGREGATE GROUND LIMESTONE 2 TON/ACRE	MULCH METHOD 2 2 TONS/ACRE	TEMP. EROSION CONTROL SEEDING • 100 LBS/ACRE/APPL
	ACRE	POUND	FOOT	FOOT	TON	SQ. FT.	POUND
C.H. 12	1.63	146.7	146.7	146.7	3.26	3.26	327
TOTAL PROJECT	1.63	146.7	146.7	146.7	3.26	3.26	327
USE	1.63	147	147	147	3.3	3.3	327

	Rice, Berry and Associates A Division of Hampton, Lenzini and Renwick, Inc. Civil & Structural Engineers 801 S. Durkin Drive Springfield, Illinois 62704 217-546-3400	ROADWAY SCHEDULE OF QUANTITIES SECTION 00-00075-00-PV C.H. 12 FARMERSVILLE ROAD MACOUPIN COUNTY
	Account Number 03-61-0002-1 Date: 03/10/05 DESIGNED: L.F.S. CHECKED: L.F.S. DRAWN: TWK	