

ROUTE NO.	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
C.H. 12	00-00075-00-PV	MACOUPIN	37	5
FED. ROAD DIST. NO.		QUANTITY	FED. AID PROJECT	

GUARDRAIL SCHEDULE						
LOCATION	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	VERTICAL ADJUSTMENT OF GUARDRAIL	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REFLECTORS	STEEL PLATE BEAM GUARDRAIL REMOVAL	TERMINAL SECTION REMOVAL AND SALVAGE
	EACH	EACH	EACH	EACH	EACH	EACH
RT. STA. 67+10.5			1			
RT. STA. 67+10.5 TO RT. STA. 67+60.5	1			1		
RT. STA. 67+10.5 TO RT. STA. 67+35.5						1
RT. STA. 67+35.5 TO RT. STA. 67+60.5					25	
RT. STA. 67+60.5 TO RT. STA. 68+73		112.5		1		
RT. STA. 68+73 TO RT. STA. 68+98					25	
RT. STA. 68+98 TO RT. STA. 69+23						1
RT. STA. 68+73 TO RT. STA. 69+23	1			1		
RT. STA. 69+23			1			
LT. STA. 67+73			1			
LT. STA. 67+73 TO LT. STA. 68+23	1			1		
LT. STA. 67+73 TO LT. STA. 67+98						1
LT. STA. 67+98 TO LT. STA. 68+23					25	
LT. STA. 68+23 TO LT. STA. 69+35.5		112.5		1		
LT. STA. 69+35 TO LT. STA. 69+60.5					25	
LT. STA. 69+60.5 TO LT. STA. 69+85.5						1
LT. STA. 69+35.5 TO LT. STA. 69+85.5	1			1		
LT. STA. 69+85.5			1			
LT. STA. 153+40			1			
LT. STA. 153+40 TO LT. STA. 153+90	1			1		
LT. STA. 153+40 TO LT. STA. 153+65						1
LT. STA. 153+65 TO LT. STA. 153+90					25	
LT. STA. 153+90 TO LT. STA. 155+02.5		112.5		1		
LT. STA. 155+02.5 TO LT. STA. 155+27.5					25	
LT. STA. 155+27.5 TO LT. STA. 155+52.5						1
LT. STA. 155+02.5 TO LT. STA. 155+52.5	1			1		
LT. STA. 155+52.5			1			
RT. STA. 153+77.5			1			
RT. STA. 153+77.5 TO RT. STA. 154+27.5	1			1		
RT. STA. 153+77.5 TO RT. STA. 154+02.5						1
RT. STA. 154+02.5 TO RT. STA. 154+27.5					25	
RT. STA. 154+27.5 TO RT. STA. 154+40		12.5				
RT. STA. 154+40 TO RT. STA. 154+65					25	
RT. STA. 154+65 TO RT. STA. 154+90						1
RT. STA. 154+40 TO RT. STA. 154+90	1			1		
RT. STA. 154+90			1			
RT. STA. 187+21.5			1			
RT. STA. 187+21.5 TO RT. STA. 187+71.5	1			1		
RT. STA. 187+21.5 TO RT. STA. 187+46.5						1
RT. STA. 187+46.5 TO RT. STA. 187+71.5					25	
RT. STA. 187+71.5 TO RT. STA. 188+84		112.5		1		
RT. STA. 188+84 TO RT. STA. 189+09					25	
RT. STA. 189+09 TO RT. STA. 189+34						1
RT. STA. 188+84 TO RT. STA. 189+34	1			1		
RT. STA. 189+34			1			
LT. STA. 188+49			1			
LT. STA. 188+49 TO LT. STA. 188+99	1			1		
LT. STA. 188+49 TO LT. STA. 188+74						1
LT. STA. 188+74 TO LT. STA. 188+99					25	
LT. STA. 188+99 TO LT. STA. 190+11.5		112.5		1		
LT. STA. 190+11.5 TO LT. STA. 190+36.5					25	
LT. STA. 190+36.5 TO LT. STA. 190+61.5						1
LT. STA. 190+11.5 TO LT. STA. 190+61.5	1			1		
LT. STA. 190+61.5			1			
TOTAL	12	575	12	17	300	12

HLR
 Rice, Berry and Associates
 A Division of Hampton,
 Lenzini and Renwick, Inc.
 Civil & Structural Engineers
 801 S. Durkin Drive
 Springfield, Illinois 62704
 217-546-3400
 P.O. BOX 1036
 DuQuoin, Illinois 62832
 618-790-4637

Account Number
 03-61-0002-1
 Date: 03/10/05

DESIGNED: L.F.S. CHECKED: L.F.S. DRAWN: TWK

ROADWAY
 SCHEDULE OF QUANTITIES
 SECTION 00-00075-00-PV
 C.H. 12 FARMERSVILLE ROAD
 MACOUPIN COUNTY