

1 2 3 4 5 6 7 8 9 MKS 2/8/05
 10 11 12 13 14 15 16 17 18 \94652d\02010pa.dgn
 19 20 21 22 23 24 25 26 SUP REV: 05-04-98
 27 28 29 30 31 32 33 34 35
 36 37 38 39 40 41 42 43 44 45
 46 47 48 49 50 51 52 53 54
 55 56 57 58 59 60 61 62 63

SUMMARY OF QUANTITIES

FAP RTL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(1012)W.RS	WHITE/ EDWARDS	118	5
FED. ROAD DIST. NO. 1		BALANCE	FED. AID PROJECT NO.	
CONTRACT NO. 94652				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	80% FED./20% STATE		CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		WHITE COUNTY 1000-2A	EDWARDS COUNTY 1000-2A	80% STATE 20% CITY WHITE SFTY-1B	80% STATE 20% CITY EDWARDS SFTY-1B		100% CITY EDWARDS SFTY-1B
54216267	REINFORCED CONCRETE PIPE TEE, 27" PIPE WITH 15" RISER	EACH	5		5				
60278130	MANHOLES, SANITARY, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1				
X0324975	PARKING RAIL REMOVAL	FOOT	238	82	156				
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	407	284	123				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	862	358	504				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	3		3				
20200100	EARTH EXCAVATION	CU YD	1912	144	1768				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	944	161	783				
20300100	CHANNEL EXCAVATION	CU YD	75	75					
20400800	FURNISHED EXCAVATION	CU YD	10267	2811	7456				
20800150	TRENCH BACKFILL	CU YD	1889	173	1716				
21400100	GRADING AND SHAPING DITCHES	FOOT	45		45				
25000100	SEEDING, CLASS 1	ACRE	3	0.5	2.5				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	268	40	228				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	268	40	228				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	268	40	228				
25000700	AGRICULTURAL GROUND LIMESTONE	TON	6	1	5				
25100105	MULCH, METHOD 1	ACRE	3	0.45	2.55				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	295	45	250				
28000300	TEMPORARY DITCH CHECKS	EACH	16		16				
28000400	PERIMETER FROSTION BARRIER	FOOT	1943	310	1633				
28000500	INLET AND PIPE PROTECTION	EACH	108	12	96				
28100105	STONE RIPRAP, CLASS A3	SQ YD	115	37	78				
28200200	FILTER FABRIC	SQ YD	160	52	108				
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	304	32	272				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	293	8	285				
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	3162	234	2928				
40500300	BITUMINOUS MIXTURE COMPLETE	TON	72	2	70				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2451	370	2081				
40600300	AGGREGATE (PRIME COAT)	TON	49	8	41				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

\94652d\02010pa.dgn
 MKS 2/8/05