

CONTRACT NO. 94827

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
940+67.23	75.00' RT	1
940+63.25	85.00' LT	1
944+00.00	85.00' LT	1
948+00.00	90.00' LT	1
951+00.00	90.00' LT	1
953+00.00	70.00' LT	1
954+69.89	75.00' RT	1
955+58.25	290.90' RT	1
955+77.24	283.13' RT	1
955+81.36	79.11' RT	1
956+18.00	65.00' RT	1
957+79.93	70.00' LT	1
958+39.93	70.00' LT	1
966+00.00	65.00' RT	1
966+50.00	70.00' RT	1
969+02.77	70.00' LT	1
969+71.52	60.00' LT	1
970+00.00	70.00' RT	1
970+20.00	60.00' RT	1
974+39.81	60.00' RT	1
975+00.76	60.00' RT	1
977+16.53	60.00' LT	1
977+64.83	60.00' RT	1
977+76.41	70.00' LT	1
980+41.10	80.00' LT	1
980+00.00	70.00' LT	1
990+85.78	118.66' RT	1
991+79.02	207.17' RT	1
991+93.07	192.70' RT	1
996+50.00	100.00' LT	1
996+50.00	120.00' LT	1
998+00.00	100.00' LT	1
1000+00.00	120.00' RT	1
1005+50.00	120.00' RT	1
1005+50.00	140.00' RT	1
1005+50.00	120.00' LT	1
1005+50.00	140.00' LT	1
1011+00.00	114.60' RT	1
1011+00.00	140.00' RT	1
1012+62.89	140.00' LT	1
1015+36.34	110.00' LT	1
1007+34.85	1017.10' LT	1
1007+50.35	1027.49' LT	1
1007+78.91	976.92' LT	1
1008+71.08	852.38' LT	1
1011+41.50	579.44' LT	1
1011+54.43	594.11' LT	1
1013+89.02	372.41' LT	1
1014+27.74	332.44' LT	1
1014+59.54	291.13' LT	1
1014+61.87	357.16' LT	1
1014+91.38	314.19' LT	1
1015+27.37	143.62' LT	1
1019+28.10	110.00' LT	1
1019+28.10	110.00' RT	1
1020+00.00	110.00' RT	1
TOTAL 56		

TIE BARS

STATION TO STATION	OFFSET	EACH
1026+06.00	1033+86.00	LT
		TOTAL 391

RELOCATE EXISTING MAILBOX

LOCATION	STATION	OFFSET	EACH
MAINLINE	953+43.87	LT	1
MAINLINE	967+27.95	LT	1
MAINLINE	970+60.35	RT	1
MAINLINE	972+51.24	RT	1
MAINLINE	973+13.35	LT	1
MAINLINE	977+64.71	RT	1
MAINLINE	982+32.80	RT	1
MAINLINE	1022+28.92	LT	1
MAINLINE	1024+10.00	LT	6
WEBB ST.	241+07.92	LT	1
COUNTRY EST.	105+96.86	LT	1
WOODBIRD	158+33.21	LT	1
WOODBIRD	158+39.84	LT	1
TOTAL 18			

REMOVE RIGHT-OF-WAY MARKERS

STATION	OFFSET	EACH
956+18.98	RT	1
980+40.55	LT	1
1019+27.90	LT	1
1020+52.46	RT	1
1021+02.89	LT	1
1021+30.02	LT	1
1021+39.99	LT	1
1022+02.77	RT	1
1026+00.19	LT	1
1034+97.34	LT	1
1034+98.42	LT	1
1037+54.11	RT	1
1037+73.63	RT	1
1037+75.06	RT	1
TOTAL 14		

FURNISH RIGHT-OF-WAY MARKERS, SPECIAL

STATION	OFFSET	EACH
1020+50.00	RT	1
1021+75.00	LT	1
1022+00.00	RT	1
1023+35.57	LT	1
1023+41.40	LT	1
1023+96.23	LT	1
1025+62.92	LT	1
1025+74.43	LT	1
1026+01.10	LT	1
1026+16.34	LT	1
1027+00.00	RT	1
1027+62.97	RT	1
1030+50.00	LT	1
1030+71.01	RT	1
1031+00.00	LT	1
1034+00.00	RT	1
1034+00.00	RT	1
1034+32.00	LT	1
1034+32.00	LT	1
1034+52.87	RT	1
1035+00.00	LT	1
1035+78.79	LT	1
1038+00.00	LT	1
1038+34.97	RT	1
1039+00.00	RT	1
40+00.00	RT	1
40+47.48	LT	1
40+50.00	RT	1
41+64.27	RT	1
41+65.68	RT	1
41+73.56	RT	1
43+84.39	RT	1
43+85.53	RT	1
TOTAL 33		

BITUMINOUS BASE COURSE, SUPERPAVE, 6"

LOCATION	STATION TO STATION	OFFSET	SO. YD.
1200TH ST.	200+78.07	202+00.00	LT&RT 298
1200TH CONN.	300+11.00	302+21.59	LT&RT 571
WOODBIRD	297+30.74	299+38.92	LT&RT 580
WOODBIRD	308+74.14	309+88.00	LT&RT 334
TOTAL 1783			

BITUMINOUS BASE COURSE, SUPERPAVE, 8"

LOCATION	STATION TO STATION	OFFSET	SO. YD.
NAZARENE	82+36.29	83+65.10	RT 33
NAZARENE	83+65.10	84+56.47	RT 169
TOTAL 202			

(SEE RURAL ENTRANCE SCHEDULE FOR REMAINING QUANTITIES)

BITUMINOUS BASE COURSE, SUPERPAVE, 9 1/2"

LOCATION	STATION TO STATION	OFFSET	SO. YD.
NAZARENE	955+36.99	955+5658	RT 8
TOTAL 8			

BITUMINOUS BASE COURSE, SUPERPAVE, 1 1/4"

STATION TO STATION	OFFSET	SO. YD.
942+50.00	981+19.93	LT&RT 15480
981+19.93	995+37.93	LT&RT 5041
995+37.93	1007+60.00	LT&RT 5057
1007+60.00	1016+00.00	LT&RT 2637
1016+00.00	1023+19.93	LT&RT 2118
1023+19.93	1034+00.00	LT&RT 4560
1034+00.00	1039+00.00	LT&RT 2000
39+00.00	40+10.00	LT&RT 440
40+10.00	41+31.63	LT&RT 357
41+31.63	43+93.20	LT&RT 409
43+93.20	46+80.05	RT 215
TOTAL 38314		

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70

LOCATION	STATION TO STATION	OFFSET	TONS
MAINLINE	942+50.00	1016+00.00	LT&RT 5472
MAINLINE	1016+00.00	1039+00.00	LT&RT 1588
NAZARENE	82+36.29	84+56.47	LT&RT 103
1200TH ST.	200+73.94	213+00.00	LT&RT 33
1200TH CONN.	300+11.00	302+21.59	LT&RT 64
WOOD BIRD	297+30.74	299+38.92	LT&RT 65
WOOD BIRD	308+74.14	309+88.00	LT&RT 37
TOTAL 7362			

(SEE RURAL ENTRANCE SCHEDULE FOR REMAINING QUANTITIES)

POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90

LOCATION	STATION TO STATION	OFFSET	TONS
MAINLINE	39+00.00	46+80.05	LT&RT 599
TOTAL 599			

LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70

LOCATION	STATION TO STATION	OFFSET	TONS
MAINLINE	942+50.00	1016+00.00	LT&RT 905
MAINLINE	1016+00.00	1039+00.00	LT&RT 231
TOTAL 1136			

LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N90

LOCATION	STATION TO STATION	OFFSET	TONS
MAINLINE	39+00.00	46+80.05	LT&RT 160
TOTAL 160			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SHEET 4 OF 4

DRAWN BY ASB
CHECKED BY SJK

DATE 03/03