

teesleyck  
3/31/2005  
c:\projects\94905\d04201pa.dgn  
SOQ2

# SUMMARY OF QUANTITIES

FBI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	141-TIRS-1	JEFFERSON	48	5
FED. ROAD DIST. NO. 7		BALDWIN		FED. AID PROJECT NO.
CONTRACT NO. 94905				

SUMMARY OF QUANTITIES			90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000	X771-2A 041-0069	X771-2A 041-0080		
50300225	CONCRETE STRUCTURES	CU YD	8.5		7	1.5		
50300260	BRIDGE DECK GROOVING	SQ YD	1970		1304	666		
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28		20	8		
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	14		14			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4480		4170	310		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1980		1580	400		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	248	248				
60107700	PIPE UNDERDRAINS 6"	FOOT	119430	119430				
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	4570	4570				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1700	1700				
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	87.5	87.5				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	16	12		4		
63200307	STEEL PLATE BEAM GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	87.5	87.5				
63200310	GUARDRAIL REMOVAL	FOOT	1296	1196		100		
63500105	DELINEATORS	EACH	275	275				
63500120	DELINEATOR REMOVAL	EACH	252	252				
64200105	SHOULDER RUMBLE STRIP	FOOT	106587	106587				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10				
67100100	MOBILIZATION	L SUM	1	1				
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1			1		
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1	1				
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		0.5	0.5		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1				
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY