

teasleyck  
3/31/2005  
c:\projects\94905d\04201pa.dgn  
QUSCHG

FAI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7RS-1	JEFFERSON	48	28
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94905

BITUMINOUS SCHEDULE

LOCATION	TEMPORARY RAMP SQ YD	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH) SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GAL	AGGREGATE (PRIME COAT) TON	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX"C", N70 TON
041-0069					
STAGE I	35.0	232	24	2	12
STAGE II	35.0	232	24	2	12
TOTAL	70	464	48	4	24

BRIDGE REPAIR SCHEDULE

LOCATION	LENGTH FEET	BITUMINOUS CONCRETE REMOVAL (DECK) SQ YD	BRIDGE DECK HYDRO- SCARIFICATION 1/2 IN SQ YD	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4 IN SQ YD	BRIDGE DECK GROOVING SQ YD	PLUG EXISTING DECK DRAINS EACH	POLYMER CONCRETE CY FT	SILICONE JOINT SEALER, 1.5 IN LIN FT	FORMED CONCRETE REPAIR <= 5 IN SQ FT	DECK SLAB REPAIR (FULL DEPTH, TYPE II) SQ YD
041-0069										
Stage I	247	707	707	707	652	2	4.38	72.0		
Stage II	247	707	707	707	652	2	4.38	72.0		2
TOTAL		1414	1414	1414	1304	4	8.8	144	14	2

COMBINATION CURB AND GUTTER REMOVAL

LOCATION	LENGTH (FT)
55+55.0 TO 55+91.17 3' LT.	36.17
55+55.0 TO 55+91.17 9' LT.	36.17
44+16.58 TO 44+53.00 3' RT.	36.42
44+16.58 TO 44+53.00 9' RT.	36.42
TOTAL=	145.18

MEDIAN REMOVAL

LOCATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (SQ FT)
43+87.75 TO 44+16.58	28.83	5.48	158.0
44+16.58 TO 44+53.0	36.42	3.67	133.5
55+55.0 TO 55+91.17	36.17	3.67	132.6
55+91.17 TO 56+20.0	28.83	5.48	158.0
TOTAL=			582.1

TEMPORARY PAVEMENT

LOCATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (SQ YD)
43+87.75 TO 44+16.58	29	6	19.2
44+16.58 TO 44+53.0	36	6	24.3
55+55.0 TO 55+91.17	36	6	24.1
55+91.17 TO 56+20.0	29	6	24.1
TOTAL=			91.7

PCC BASE COURSE WIDENING, 8"

LOCATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (SQ YD)
43+87.75 TO 44+01.00	13	6	8.8
44+01.00 TO 44+53.00	52	1	5.8
55+55.00 TO 56+07.00	52	1	5.8
56+07.00 TO 56+20.0	13	6	8.7
TOTAL=			29.1

CONCRETE MEDIAN, TYPE SM-4.06

LOCATION	LENGTH FEET	WIDTH FEET	QUANTITY SQ FT
44+01.00 TO 44+53.00	52.00	VAR.	256.3
55+55.00 TO 56+07.00	52.00	VAR.	256.3
TOTAL			512.6

PAVEMENT MARKING SCHEDULE

LOCATION	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	SHORT TERM PAVEMENT MARKING FEET	TEMPORARY PAVEMENT MARKING - LINE 4" FEET	PAINT PAVEMENT MARKING - LINE 4" FEET
041-0069				
STAGE I =	86	327	327	327
STAGE II =	402	0	327	327
TOTAL	489	327	654	654

FORMED CONCRETE REPAIR DEPTH  
EQUAL TO OR LESS THAN 5"

STRUCTURE	LOCATION	QUANTITY SQ FT
041-0069	South Abutment	3
	North Abutment	11
	TOTAL	14

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

QUANTITY SCHEDULES  
S.N. 041-0069

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY