

steffenmk
3/31/2005
c:\projects\94944\d01302pa.dgn

SOQ

SUMMARY OF QUANTITIES

SYL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(18,19,20) RS-2	CRAWFORD	21	3

CONTRACT NO. 94944

SUMMARY OF QUANTITIES			80% FED. 20% STATE 1000 TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	158	158	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	38640	38640	
40600300	AGGREGATE (PRIME COAT)	TON	387	387	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	300	300	
40600990	TEMPORARY RAMP	SQ YD	156	156	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	183845	183845	
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	1366	1366	
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	134	134	
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	259	259	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6067	6067	
54215553	METAL END SECTIONS 18"	EACH	1	1	
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	10	10	
63200310	GUARDRAIL REMOVAL	FOOT	30	30	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	24396	24396	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	108	108	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	145241	145241	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	170	170	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	96	96	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2033	2033	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	108	108	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	170	170	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	96	96	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	145241	145241	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	735	735	
X4066416	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	TON	15672	15672	
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	558	558	

SUMMARY OF QUANTITIES			80% FED. 20% STATE 1000 TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT			
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	7836	7836	
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	279	279	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	108	108	
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	9055	9055	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	1	1	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE