

teeslegck
5/3/2005
c:\projects\94962d\03102pa.dgn

SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
750	(114) Y. WRS	FAYETTE	74	3
FED. ROAD DIST. NO. 7		BLDGMS	FED. AID PROJECT NO.	

CONTRACT NO. 94962

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-2A	SFTY-2A	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22	22		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	85	85		
20200100	EARTH EXCAVATION	CU YD	1285.3	1285.3		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	560.8	560.8		
20400800	FURNISHED EXCAVATION	CU YD	451	451		
20800150	TRENCH BACKFILL	CU YD	1501	1501		
* 25000100	SEEDING, CLASS 1	ACRE	2.1	2.1		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	186	186		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	186	186		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	186	186		
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	4.1	4.1		
* 25100115	MULCH, METHOD 2	ACRE	2.1	2.1		
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	206	206		
* 28000300	TEMPORARY DITCH CHECKS	EACH	8	8		
* 28000500	INLET AND PIPE PROTECTION	EACH	29	29		
28100105	STONE RIPRAP, CLASS A3	SQ YD	291	291		
28200200	FILTER FABRIC	SQ YD	291	291		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	175	175		
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	880	880		
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	1948	1948		
X3550500	BITUMINOUS BASE COURSE ^{8"} SUPERPAVE,	SQ YD	165	165		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	15	15		
40500300	BITUMINOUS MIXTURE COMPLETE	TON	20	20		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1919	1902	17	
40600300	AGGREGATE (PRIME COAT)	TON	38	37	1	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	801	801		
40600990	TEMPORARY RAMP	SQ YD	194	194		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	211	211		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	53	53		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2450	2450		
44000100	PAVEMENT REMOVAL	SQ YD	594	594		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	90	90		
44000400	GUTTER REMOVAL	FOOT	409	409		
44000600	SIDEWALK REMOVAL	SQ FT	2868	2868		
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	195	195		

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000-2A	SFTY-2A	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	69	69		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	17	7	10	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	531	531		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	136	136		
50102400	CONCRETE REMOVAL	CU YD	2	2		
50104400	CONCRETE HEADWALL REMOVAL	EACH	9	9		
50105220	PIPE CULVERT REMOVAL	FOOT	1486	1486		
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2		
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2		
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2		
54020602	PRECAST CONCRETE BOX CULVERT 6' X 2' (M273)	FOOT	10	10		
54213450	END SECTIONS 15"	EACH	9	9		
54215571	METAL END SECTIONS 36"	EACH	2	2		
54248515	CONCRETE COLLAR	EACH	6	6		
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	42	42		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	555	555		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	64	64		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	157	157		
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	155	155		
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	524	524		
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	782	782		
* 550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	160	160		
* 550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	162	162		
* 550A2380	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 30"	FOOT	269	269		
550B0010	STORM SEWERS, CLASS B, TYPE 1 4"	FOOT	30	30		
550B0020	STORM SEWERS, CLASS B, TYPE 1 6"	FOOT	30	30		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	9		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		

* SPEC

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DATE HORIZ. DATE

DRAWN BY _____
CHECKED BY _____