



DATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TR 1/25	04-68111-00-BK	WABASH	13	6
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	



95419



TYPICAL ELEVATIONS




PLAN




Beam	W	Wo
36"	2'-1"	1'-0 1/2"
48"	2'-5"	1'-2 1/2"


1/2" FABRIC BRG. PAD DETAILS




PROFILE OF OVERLAY



CROSS SECTION



CROSS SECTION



SECTION AT ABUTS.
(Along centerline Beams)

SECTION AT PIERS
(Along centerline Beams)

QUANTITIES FOR ONE SPAN

P.P.C. Conc. Dk. Bm. 27" Dp.	1440 Sq. Ft.
Steel Railing	120 Ft.
Bit. Conc. Surf. Cse. Class I	18.8 Tons
Waterproofing Membrane System	160.0 Sq. Yds.

NOTES

- After beams have been erected, holes shall be drilled into substructure and anchor dowels placed. Dowel holes shall be filled with ~~non-shrink~~ grout to top of beam and allowed to cure min. 24 hrs. prior to grouting the shear keys.
- Nominal 1" joint at centerline Pier shall be filled with ~~non-shrink~~ grout.
- Longitudinal keys shall be grouted.
- The 1" phi rods in the transverse tie assembly shall be tightened to a snug fit and the threads set. Pockets that receive transverse tie bar outside shall be filled with grout after transverse tie assembly is in place.

Illinois Department of Transportation
 PASSED NOVEMBER 1, 1995
 [Signature]
 Engineer of Bridge Design
 APPROVED NOVEMBER 1, 1995
 [Signature]
 Engineer of Bridges and Structures

P.P.C. DECK BEAM
 SUPERSTRUCTURE
 24' RDWY. 27" BMS. 60' SPAN 0° SKEW
 STANDARD CS-2427-60