

F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
869	(103)	SALINE	64	9
STA.		TO STA.		
FED. ROAD DIST. NO. -		ILLINOIS	FED. AID PROJECT	
CONTRACT NO.: 98896				

### ENTRANCE SCHEDULE

LOCATION STATION	EXISTING ENTRANCE			PROPOSED ENTRANCE				BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	AGGREGATE BASE COURSE, TYPE A TON	AGGREGATE SURFACE COURSE, TYPE A TON	INCIDENTAL BITUMINOUS SURFACING TON
	TYPE	SURFACE	WIDTH	WIDTH	RADIUS	LENGTH	AREA					
				FOOT	FOOT	FOOT	SQ FT					
IL 34												
SALINE COUNTY												
RURAL												
STA 1027+50.0	P.E.L.	AGG.	13	13	15	41.3	633.5	3.3	0.02	2.3	20.5	1.1
STA 1030+29.4	P.E.L.	AGG.	12	12	15	38.0	552.6	3.2	0.01	2.3	17.6	1.1
STA 1033+21.2	P.E.L.	AGG.	10	12	15	15.0	279.1	3.2	0.01	2.3	7.2	1.1
STA 1033+24.6	P.E.R.	BIT.	12	12	15	15.0	276.6	3.2	0.01	2.3	7.1	1.1
STA 1034+83.6	C.E.L.	AGG.	26	26	25	24.7	918.3	32.6	0.15	23.1		11.4
STA 1042+53.3	P.E.L.	AGG.	10	12	15	41.8	598.2	3.2	0.01	2.3	19.3	1.1
STA 1050+12.6	F.E.L.	AGG.	14	14	15	42.7	694.4	3.4	0.02	2.4	22.7	1.2
STA 1052+28.3	F.E.L.	AGG.	11									
STA 1053+64.3	P.E.L.	AGG.	14	14	15	31.1	532.0	3.4	0.02	2.4	16.6	1.2
STA 1053+91.8	F.E.R.	AGG.	22	22	15	38.0	932.6	4.2	0.02	3.0	30.9	1.5
STA 1059+32.0	P.E.L.	AGG.	12	12	15	22.5	369.2	3.1	0.02	2.3	10.1	1.1
STA 1059+96.0	F.E.L.	EARTH	0	22	15	22.0	580.6	4.2	0.01	3.3		1.5
FROM SURFACING SCHEDULE								2,793.0	18.30			
PROJECT TOTALS:								2,860.0	18.60	48.0	152.0	23.4

### ENTRANCE CULVERT SCHEDULE

LOCATION STATION	EXISTING ENTRANCE	PIPE CULVERTS.			END SECTIONS 15" EACH	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" EACH	PIPE CULVERT REMOVAL * FOOT
		CLASS A TYPE 1 18" FOOT	CLASS D				
			TYPE 1 15" FOOT	TYPE 2 15" FOOT			
IL 34							
SALINE COUNTY							
RURAL							
STA 1027+50.0	P.E.L.		33		2		
STA 1030+29.4	P.E.L.			126	2		
STA 1033+21.2	P.E.L.				2		
STA 1033+24.6	P.E.R.						
STA 1034+83.6	C.E.L.		38		2	48	
STA 1042+53.3	P.E.L.			34	2		
STA 1050+12.6	F.E.L.			54	2		
STA 1053+64.3	P.E.L.			41	2		
STA 1053+91.8	F.E.R.						
STA 1059+32.0	P.E.L.			32	2		
STA 1059+96.0	F.E.L.			33	2		
FROM DRAINAGE SCHEDULE				35			
PROJECT TOTALS:		38	173	215	14	48	

\* EXISTING RCCP

DATE TIME: FEBRUARY 4, 2006  
DRAWN: SPEC: d903502 v9505502sch.m32