

**EROSION CONTROL NOTES:**

1. ALL PROPOSED EROSION CONTROL MEASURES SHALL BE COMPLETED AS STATED ON THIS STORM WATER POLLUTION PREVENTION PLAN AND IN ACCORDANCE WITH THE SPECIFICATIONS. EROSION CONTROL DETAILS ARE LOCATED ON SHEET 5 OF THESE CONSTRUCTION PLANS.
2. EROSION CONTROL MEASURES ARE COVERED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY'S STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL.
3. STRAW BALES SHALL BE USED FOR DITCH CHECKS AS SHOWN ON THE DETAILS AND AS SPECIFIED IN THE SPECIAL PROVISIONS.
4. ALL STRAW BALES PLACED ON THIS PROJECT SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4 INCHES, SHALL BE STAKED TO THE GROUND, AND SHALL BE PLACED SO THE BINDINGS ARE HORIZONTAL.
5. DITCH CHECKS SHALL BE PLACED APPROXIMATELY EVERY 500-FT IN ALL EXISTING AND PROPOSED DITCHES AS SHOWN ON THIS SHEET. DITCH CHECKS SHALL BE PAID FOR AS ITEM AR156511-DITCH CHECK.

6. APPROXIMATELY 9 STRAW BALES SHALL BE REQUIRED PER DITCH CHECK. FOR BIDDING PURPOSES APPROXIMATELY 6 DITCH CHECKS SHALL BE CONSTRUCTED, MAINTAINED, AND REMOVED BY THE CONTRACTOR.
7. INSPECTION OF THE STRAW BALES WILL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE FREQUENT. REPAIR/REPLACEMENT SHALL BE COMPLETED BY THE CONTRACTOR AS NEEDED IN A TIMELY MANNER. AT A MINIMUM, STRAW BALES SHALL BE REPLACED EVERY 3 MONTHS OR WHEN DIRECTED BY THE RESIDENT ENGINEER.
8. STRAW BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS SO AS NOT TO BLOCK OR IMPEDE STORM WATER DRAINAGE.
9. WHEN CONSTRUCTION ACTIVITIES ARE TO TEMPORARILY CEASE FOR A PERIOD OF 21 OR MORE CALENDAR DAYS, GRADED OR CLEARED AREAS SHALL BE TEMPORARILY SEEDED WITHIN 14 DAYS OF SUSPENSION OF WORK. TEMPORARY SEEDING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SPECIFICATION AND PAID FOR AS ITEM AR156530-TEMPORARY SEEDING.

HARRISBURG-RALEIGH AIRPORT  
 IL PROJECT NO. HSB-3422  
 AIP NO. 3-17-0050-B6  
 STORM WATER POLLUTION PREVENTION PLAN  
**SHEET 4 OF 24**  
 HA020

