



REMOVE & REPLACE BITUMINOUS PAVEMENT

THE AREA DESIGNATED AS ON THIS SHEET WILL HAVE THE EXISTING PAVEMENT REMOVED (FULL DEPTH) TO A SUITABLE SUBGRADE. ALL REMOVED MATERIAL WILL BE DISPOSED OF OFF THE AIRPORT SITE.

WHERE THE PROPOSED REMOVAL AREA ABUTS THE EXISTING PAVEMENT, THE PAVEMENT WILL BE SAWED AS SHOWN ON THIS SHEET. THE SAWING WILL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE PROPOSED PAVEMENT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE AGGREGATE BASE COURSE AND BITUMINOUS SURFACE COURSE WILL BE INSTALLED AS PER THE SUPPLEMENTAL SPECIFICATIONS. THESE ITEM ARE CONSIDERED A PART OF THIS PAY ITEM AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE RESIDENT ENGINEER WILL LAYOUT THE LIMITS OF THE PAVEMENT REMOVAL AND REPLACEMENT. ANY ADJACENT PAVEMENT DAMAGED BY THE PAVEMENT REMOVAL OPERATIONS WILL BE REPAIRED AT THE CONTRACTOR'S OWN EXPENSE.

THE REMOVAL AND REPLACEMENT OF BITUMINOUS PAVEMENT WILL BE PAID FOR UNDER ITEM: AR401910 "REMOVE & REPLACE BITUMINOUS PAVEMENT" _____ 141 SQ. YDS.

QUANTITIES			
ITEM NO.	DESCRIPTION	UNIT	QUANTITY
AR401910	REMOVE & REPLACE BITUMINOUS PAVEMENT	SY	141

I:\Airports\OLNEY\820-05RWY\Airport\Sheets\R-101REM.dgn 05/16/2005, 10:27 AM mew

REVISION		DATE			
<p>OLNEY-NOBLE AIRPORT OLNEY, ILLINOIS RICHLAND COUNTY</p>					
<p>FILE PROJECT No. 820-05RWY FILENAME R-101REM.DGN SCALE 1" = 30' DATE 02/03/05</p>					
LAYOUT		JAC		02/03/05	
DRAWN		JAC		02/03/05	
REVIEWED		CAH		05/13/05	
			<p>Hanson Professional Services Inc. 4227 Earth City Expressway, Suite 130 St. Louis, MO 63046-3308 Offices Nationwide</p>		
<p>REHABILITATE RUNWAY 3/21</p>			<p>PROPOSED PAVEMENT REMOVAL AND REPLACEMENT</p>		
<p>4</p>					
<p>4 of 38 sheets</p>					