



**SCHEDULE OF INTERCONNECT QUANTITIES**

QUANTITY	UNIT	ITEM
6574	FOOT	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL
1131	FOOT	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL
8	EACH	HANDHOLE
6574	FOOT	TRENCH AND BACKFILL FOR ELECTRICAL WORK
2	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
1	EACH	MASTER CONTROLLER (SPECIAL)
5341	FOOT	REMOVE ELECTRIC CABLE FROM CONDUIT
1	EACH	REMOVE EXISTING HANDHOLE
14575	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C
8	EACH	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL 2
14809	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

Rev. 6-8-11

FILE NAME = \$FILEL\$	USER NAME = \$USER\$	DESIGNED - PKG	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PROPOSED INTERCONNECT SCHEMATIC US RTE. 20 (LAKE AVE.) FROM MARCUS CINEMA DR/FOX LAKE COMMONS TO ITASCA RD. (SHEET 2 OF 2)</b>			F.A.P. RTE. 2578	SECTION 532B	COUNTY DuPage	TOTAL SHEETS 781	SHEET NO. 541A
	PLOT SCALE = \$SCALE\$	CHECKED - PKG, EA	REVISED -		SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60477	
	PLOT DATE = \$DATE\$	DATE - 5/18/2011	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							