



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 9, 2011

SUBJECT: FAP Route 305 (US 14)
Project CMF-0305 (044)
Section 24 R-N-2
Lake County
Contract No. 60K17
Item No. 287, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 138 to the Special Provisions.
4. Revised sheet 5 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| XX004913 | REMOV FOC FR CONDUIT | FOOT | 1,034.000 | | | | |
| X0322118 | REM CON FLAR END SEC | EACH | 1.000 | | | | |
| X0324085 | EM VEH P S LSC 20 3C | FOOT | 585.000 | | | | |
| X2020110 | GRADING & SHAP SHLDRS | UNIT | 17.000 | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1.000 | | | | |
| Z0030850 | TEMP INFO SIGNING | SQ FT | 77.100 | | | | |
| Z0033046 | RE-OPTIMIZE SIG SYS 2 | EACH | 1.000 | | | | |
| Z0073510 | TEMP TR SIGNAL TIMING | EACH | 1.000 | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 675.000 | | | | |
| 20201200 | REM & DISP UNS MATL | CU YD | 671.000 | | | | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 368.000 | | | | |
| 21101625 | TOPSOIL F & P 6 | SQ YD | 2,945.000 | | | | |
| 25000210 | SEEDING CL 2A | ACRE | 0.600 | | | | |
| 25000400 | NITROGEN FERT NUTR | POUND | 55.000 | | | | |
| 25000600 | POTASSIUM FERT NUTR | POUND | 55.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 25100630 | EROSION CONTR BLANKET | SQ YD | 2,810.000 | | | | |
| 28000250 | TEMP EROS CONTR SEED | POUND | 60.000 | | | | |
| 28000305 | TEMP DITCH CHECKS | FOOT | 30.000 | | | | |
| 28000400 | PERIMETER EROS BAR | FOOT | 670.000 | | | | |
| 28000500 | INLET & PIPE PROTECT | EACH | 1.000 | | | | |
| 31101200 | SUB GRAN MAT B 4 | SQ YD | 555.000 | | | | |
| 35300600 | PCC BSE CSE 11 | SQ YD | 555.000 | | | | |
| 40600200 | BIT MATLS PR CT | TON | 4.000 | | | | |
| 40600300 | AGG PR CT | TON | 16.000 | | | | |
| 40600400 | MIX CR JTS FLANGEWYS | TON | 12.000 | | | | |
| 40600635 | LEV BIND MM N70 | TON | 40.000 | | | | |
| 40600895 | CONSTRUC TEST STRIP | EACH | 1.000 | | | | |
| 40600982 | HMA SURF REM BUTT JT | SQ YD | 132.000 | | | | |
| 40603595 | P HMA SC "F" N90 | TON | 808.000 | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 555.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|---------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 44000156 | HMA SURF REM 1 3/4 | SQ YD | 7,696.000 | | | | |
| 44300200 | STRIP REF CR CON TR | FOOT | 670.000 | | | | |
| 48101500 | AGGREGATE SHLDS B 6 | SQ YD | 460.000 | | | | |
| 48102100 | AGG WEDGE SHLD TYPE B | TON | 52.000 | | | | |
| 48203029 | HMA SHOULDERS 8 | SQ YD | 1,063.000 | | | | |
| 54213663 | PRC FLAR END SEC 18 | EACH | 1.000 | | | | |
| 54247110 | GRATING-C FL END S 18 | EACH | 1.000 | | | | |
| 55100900 | STORM SEWER REM 18 | FOOT | 65.000 | | | | |
| 67000400 | ENGR FIELD OFFICE A | CAL MO | 9.000 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1.000 | | | | |
| *ADD 66900200 | NON SPL WASTE DISPOSL | CU YD | 680.000 | | | | |
| *ADD 66900450 | SPL WASTE PLNS/REPORT | L SUM | 1.000 | | | | |
| *ADD 66900530 | SOIL DISPOSAL ANALY | EACH | 5.000 | | | | |
| 70100320 | TRAF CONT-PROT 701422 | L SUM | 1.000 | | | | |
| 70102630 | TR CONT & PROT 701601 | L SUM | 1.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 70102635 | TR CONT & PROT 701701 | L SUM | 1.000 | | | | |
| 70103815 | TR CONT SURVEILLANCE | CAL DA | 10.000 | | | | |
| 70106800 | CHANGEABLE MESSAGE SN | CAL MO | 1.000 | | | | |
| 70300100 | SHORT TERM PAVT MKING | FOOT | 3,504.000 | | | | |
| 70300210 | TEMP PVT MK LTR & SYM | SQ FT | 219.000 | | | | |
| 70300220 | TEMP PVT MK LINE 4 | FOOT | 4,107.000 | | | | |
| 70300240 | TEMP PVT MK LINE 6 | FOOT | 912.000 | | | | |
| 70300250 | TEMP PVT MK LINE 8 | FOOT | 116.000 | | | | |
| 70300260 | TEMP PVT MK LINE 12 | FOOT | 40.000 | | | | |
| 70300280 | TEMP PVT MK LINE 24 | FOOT | 100.000 | | | | |
| 70301000 | WORK ZONE PAVT MK REM | SQ FT | 390.000 | | | | |
| 72000100 | SIGN PANEL T1 | SQ FT | 34.000 | | | | |
| 72000200 | SIGN PANEL T2 | SQ FT | 55.000 | | | | |
| 78000100 | THPL PVT MK LTR & SYM | SQ FT | 219.000 | | | | |
| 78000200 | THPL PVT MK LINE 4 | FOOT | 4,107.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 78000400 | THPL PVT MK LINE 6 | FOOT | 912.000 | | | | |
| 78000500 | THPL PVT MK LINE 8 | FOOT | 116.000 | | | | |
| 78000600 | THPL PVT MK LINE 12 | FOOT | 40.000 | | | | |
| 78000650 | THPL PVT MK LINE 24 | FOOT | 100.000 | | | | |
| 78100100 | RAISED REFL PAVT MKR | EACH | 84.000 | | | | |
| 78300200 | RAISED REF PVT MK REM | EACH | 50.000 | | | | |
| 80500020 | SERV INSTALL POLE MT | EACH | 1.000 | | | | |
| 81000600 | CON T 2 GALVS | FOOT | 1,185.000 | | | | |
| 81000700 | CON T 2 1/2 GALVS | FOOT | 315.000 | | | | |
| 81000800 | CON T 3 GALVS | FOOT | 111.000 | | | | |
| 81001000 | CON T 4 GALVS | FOOT | 30.000 | | | | |
| 81018500 | CON P 2 GALVS | FOOT | 243.000 | | | | |
| 81018700 | CON P 3 GALVS | FOOT | 30.000 | | | | |
| 81018900 | CON P 4 GALVS | FOOT | 495.000 | | | | |
| 81400100 | HANDHOLE | EACH | 2.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 81400200 | HD HANDHOLE | EACH | 11.000 | | | | |
| 81400300 | DBL HANDHOLE | EACH | 2.000 | | | | |
| 81900200 | TR & BKFIL F ELECT WK | FOOT | 1,586.000 | | | | |
| 85000200 | MAIN EX TR SIG INSTAL | EACH | 1.000 | | | | |
| 85700215 | RR FAC & TY IV CAB SP | EACH | 1.000 | | | | |
| 86200120 | UNINTER POWER SUPPLY | EACH | 1.000 | | | | |
| 86400100 | TRANSCEIVER - FIB OPT | EACH | 1.000 | | | | |
| 87100020 | FOCC62.5/125 MM12SM12 | FOOT | 1,929.000 | | | | |
| 87300925 | ELCBL C TRACER 14 1C | FOOT | 1,903.000 | | | | |
| 87301225 | ELCBL C SIGNAL 14 3C | FOOT | 585.000 | | | | |
| 87301245 | ELCBL C SIGNAL 14 5C | FOOT | 2,718.000 | | | | |
| 87301255 | ELCBL C SIGNAL 14 7C | FOOT | 1,122.000 | | | | |
| 87301305 | ELCBL C LEAD 14 1PR | FOOT | 4,802.000 | | | | |
| 87301750 | ELCBL C RAILRD 14 3C | FOOT | 482.000 | | | | |
| 87301805 | ELCBL C SERV 6 2C | FOOT | 56.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE- -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|----------------------|-----------------|----------|---|------------|---|-------------|
| 87301900 | ELCBL C EGRDC 6 1C | FOOT | 879.000 | | | | |
| 87502480 | TS POST GALVS 14 | EACH | 1.000 | | | | |
| 87502490 | TS POST GALVS 15 | EACH | 1.000 | | | | |
| 87502500 | TS POST GALVS 16 | EACH | 2.000 | | | | |
| 87700180 | S MAA & P 28 | EACH | 1.000 | | | | |
| 87700260 | S MAA & P 44 | EACH | 1.000 | | | | |
| 87700270 | S MAA & P 46 | EACH | 1.000 | | | | |
| 87702930 | STL COMB MAA&P 40 | EACH | 1.000 | | | | |
| 87800100 | CONC FDN TY A | FOOT | 16.000 | | | | |
| 87800150 | CONC FDN TY C | FOOT | 4.000 | | | | |
| 87800400 | CONC FDN TY E 30D | FOOT | 15.000 | | | | |
| 87800415 | CONC FDN TY E 36D | FOOT | 45.000 | | | | |
| 87900200 | DRILL EX HANDHOLE | EACH | 1.000 | | | | |
| 88030020 | SH LED 1F 3S MAM | EACH | 7.000 | | | | |
| 88030080 | SH LED 1F 4S MAM | EACH | 1.000 | | | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K17

State Job # - C-91-443-10
 PPS NBR - 1-78092-0000
 County Name - LAKE - -
 Code - 97 - -
 District - 1 - -
 Section Number - 24 R-N-2

Project Number
 CMF-0305/044/

Route
 FAP 305

*REVISE : JUNE 6, 2011

| Item Number | Pay Item Description | Unit of Measure | Quantity | x | Unit Price | = | Total Price |
|-------------|-----------------------|-----------------|-----------|---|------------|---|-------------|
| 88030110 | SH LED 1F 5S MAM | EACH | 2.000 | | | | |
| 88030210 | SH LED 2F 3S BM | EACH | 1.000 | | | | |
| 88030230 | SH LED 2F 1-3 1-4 BM | EACH | 1.000 | | | | |
| 88030240 | SH LED 2F 1-3 1-5 BM | EACH | 2.000 | | | | |
| 88200210 | TS BACKPLATE LOU ALUM | EACH | 10.000 | | | | |
| 88500100 | INDUCTIVE LOOP DETECT | EACH | 13.000 | | | | |
| 88600100 | DET LOOP T1 | FOOT | 1,119.000 | | | | |
| 88700300 | LIGHT DETECTOR AMP | EACH | 1.000 | | | | |
| 89000100 | TEMP TR SIG INSTALL | EACH | 1.000 | | | | |
| 89501400 | REL EM VEH PR SYS D U | EACH | 3.000 | | | | |
| 89502300 | REM ELCBL FR CON | FOOT | 1,022.000 | | | | |
| 89502375 | REMOV EX TS EQUIP | EACH | 1.000 | | | | |
| 89502380 | REMOV EX HANDHOLE | EACH | 14.000 | | | | |
| 89502385 | REMOV EX CONC FDN | EACH | 10.000 | | | | |

| | |
|---|-----|
| MULCH AND EROSION CONTROL BLANKETS (BDE)..... | 111 |
| NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) | 113 |
| PAYMENTS TO SUBCONTRACTORS (BDE) | 115 |
| POST MOUNTING OF SIGNS (BDE)..... | 116 |
| PRECAST CONCRETE HANDLING HOLES (BDE)..... | 116 |
| RAISED REFLECTIVE PAVEMENT MARKERS (BDE)..... | 117 |
| SEEDING (BDE) | 117 |
| SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... | 120 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) | 121 |
| TEMPORARY EROSION CONTROL (BDE) | 121 |
| TRAFFIC CONTROL SURVEILLANCE (BDE)..... | 124 |
| TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) | 125 |
| UTILITY COORDINATION AND CONFLICTS (BDE)..... | 125 |
| WORKING DAYS (BDE) | 130 |
| BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) | 131 |
| STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) | 134 |
| REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES | 138 |

Revised 06/09/2011

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities. .

All contaminated materials shall be managed as non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a petroleum contaminated material or material contaminated by regulated substances.

A) The Environmental Firm shall continuously monitor for worker protection and the Contractor shall manage any excavated soils **within the construction limits of this project as fill.** Although the soil concentrations exceed a residential property's Tier 1 soil remediation objective for the ingestion exposure pathway, they can be utilized within the construction limits as fill because the roadway is not considered a residential property. All storm sewer excavated soils can be placed back into the excavated trench as backfill unless trench backfill is specified. If the soils cannot be utilized within the construction limits as fill then they must be managed off-site as a non-special waste. The following areas can be managed within the construction limits as fill.

1. Station 21+00 to Station 25+00 0 to 100 feet LT (Vacant Lot, Site 2062-3, 28540 West Northwest Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
2. Station 21+00 to Station 32+00 0 to 100 feet RT (Union Pacific Railroad, Site 2062-8, South of Eastbound West Northwest Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
3. Station 25+00 to Station 26+60 0 to 100 feet LT (Intersection West Northwest Highway and North Kelsey Road, Site 2062-4) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
4. Station 26+60 to Station 30+00 0 to 100 feet LT (VCA Noyes Animal Hospital, Site 2062-5, 22055 North Kelsey Road) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
5. Station 30+00 to Station 32+00 0 to 100 feet LT (Tuttle Manufacturing, Site 2062-6, 1032 West Northwest Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
6. Station 6+00 to Station 8+00 0 to 100 feet LT (Residence, Site 2062-1, 22060 North Kelsey Road) – non-special waste. Contaminants of concern sampling parameters: Arsenic.
7. Station 6+00 to Station 8+00 0 to 100 feet RT (Vacant Lot, Site 2062-3, 28540 West Northwest Highway) – non-special waste. Contaminants of concern sampling parameters: Arsenic.

Added 06/09/2011