

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0004 URBAN	RETAINING WALL 0040 URBAN
				20200100	EARTH EXCAVATION
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10	10	
20800150	TRENCH BACKFILL	CU YD	108	108	
21101615	TOPSOIL, FURNISH AND PLACE, 4"	SQ YD	6	6	
25000210	SEEDING, CLASS 2A	ACRE	0.01	0.01	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1	
25100630	EROSION CONTROL BLANKET	SQ YD	6	6	
28000305	TEMPORARY DITCH CHECKS	FOOT	16	16	
28000510	INLET FILTERS	EACH	7	7	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	55	55	
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	273	273	
44000100	PAVEMENT REMOVAL	SQ YD	309	309	
44004000	PAVED DITCH REMOVAL	FOOT	280	280	
42001300	PROTECTIVE COAT	SQ YD	98	98	
50102400	CONCRETE REMOVAL	CU YD	1.7		1.7
50300225	CONCRETE STRUCTURES	CU YD	128.7		128.7
50300300	PROTECTIVE COAT	SQ YD	390		390
50500505	SHEAR STUD CONNECTORS	EACH	405		405
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,710		12,710
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	232		232
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	425	425	
55100700	STORM SEWER REMOVAL 15"	FOOT	464	464	
60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	5	5	
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60500050	REMOVING CATCH BASINS	EACH	4	4	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	423	423	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	LSUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1596	1596	
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				ROADWAY 0004 URBAN	RETAINING WALL 0040 URBAN
				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	44	44	
* 78100300	REPLACEMENT REFLECTOR	EACH	147	147	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1528	1528	
* 81000600	CONDUIT IN TRENCH 2" DIA, GALVANIZED STEEL	FOOT	225	225	
* 81018500	CONDUIT PUSHED 2" DIA, GALVANIZED STEEL	FOOT	40	40	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1	1	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	25	25	
* 87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	1	1	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO14, 1 PR	FOOT	700	700	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	300	300	
* 87900200	DRILL EXISTING HANDHOLE	EACH	1	1	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	70	70	
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1	1	
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	3,753		3,753
* X0325815	REMOVE EXISTING CABLE FROM CONDUIT	FOOT	300	300	
X2070304	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	320		320
X5539700	STORM SEWERS TO BE CLEANED	FOOT	228	228	
X6062400	CONCRETE GUTTER (SPECIAL)	FOOT	393		393
* X6330105	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1 SPECIAL	EACH	1	1	
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	73	73	
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	3916	3916	
X7030040	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	275	275	
X7030055	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	44	44	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	273	273	
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	2,825		2,825
Z0013798	CONSTRUCTION LAYOUT	LSUM	1	1	
* Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1,145		1,145
Z0029310	GUARDRAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	17		17
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	180	180	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	418		418
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1	

* - DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = rgal1	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE. 2843	SECTION 3249-1-2	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3
		DRAWN - DR	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60L18		
		CHECKED - JMH	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE - MARCH, 2011	REVISED -										