SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	80	80					
25200110	SODDING, SALT TOLERANT	SQ YD	80	80					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	10	10					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19					
40600300	AGGREGATE (PRIME COAT)	TON	93	93					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	249	249					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	27	27					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1947	1947					
42001300	PROTECTIVE COAT	SQ YD	193	193					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20	20					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	50	50					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	23171	23171					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	30	30					
44000600	SIDEWALK REMOVAL	SQ FT	50	50					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	157	157					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	120	120					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	20	20					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	104	104					
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	27	27					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	6	6					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0005					
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	3372	3372					
	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	660	660					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13413	13413					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	977	977					
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	450	450					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	373	373					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	546	546					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7385	7385					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	660	660					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13413	13413					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	977	977					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	450	450					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	373	373					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	546	546					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	301	301					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	301	301					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	364	364					
	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	956	956					
	X5539700	STORM SEWERS TO BE CLEANED	FOOT	1200	1200					
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15					
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500					
	Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	2	2					
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	48	48					
	Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2	2					
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pw1da\pacfechal\d0234688\D1062ll-sht-plan.dgn	USER NAME = pacfechal	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/12/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE. 1 (HALSTED ST.) (152ND ST. TO US RTE. 6)
SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3730	3262-RS-3	COOK	23	3
		CONTRACT NO. 60L95		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		