

SUMMARY OF QUANTITIES				URBAN 100% STATE CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN 100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	17	17					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1500	1500				
25200110	SODDING, SALT TOLERANT	SO YD	17	17					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	500	500				
40600300	AGGREGATE (PRIME COAT)	TON	90	90					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	110	110				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	71	71				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	607	607				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	380	380					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	660	660				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	210	210					X5539700	STORM SEWERS TO BE CLEANED	FOOT	100	100				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1845	1845					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	60	60				
42001300	PROTECTIVE COAT	SO YD	25	25					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	5900	5900					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	16000	16000					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1248	1248					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	655	655													
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	264	264													
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	117	117													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2250	2250													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	122.4	122.4													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3400	3400													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1500	1500													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	600	600													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	500	500													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	250	250													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	122.4	122.4													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3400	3400													

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = gulloumep	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>				<b>SUMMARY OF QUANTITIES</b>				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\work\gulloumep\p0246826\DI09911-st-plot.dgn	DRAWN -	REVISED -	2783									2010-106-RS	COOK	19	3	
PLOT SCALE = 500000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60M32													
PLOT DATE = 4/18/2011	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT													
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.						