


CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE											
				URBAN		KANE CO. COOK CO. KANE CO.									
				KANE CO. ROADWAY	COOK CO. ROADWAY	US RTE 20 OVER FOX RIVER 045-0004	US RTE 20 OVER RAYMOND ST 045-0005	US RTE 20 OVER ST CHARLES ST 045-0006	US RTE 20 OVER IL RTE 25 045-0007	US RTE 20 OVER POPLAR CREEK 016-0217	US RTE 20 OVER US BUS US 20 016-0218	IL RTE 31 OVER US RTE 20 045-0017	FA 426 OVER WB US RTE 20 045-0008		
0005	0005	0014	0014	0014	0014	0014	0014	0014	0014	0014					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	310	250	60	-	-	-	-	-	-	-	-	-	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 IN.)	SO. FT.	499	-	-	10	27	-	-	6	55	-	-	401	
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 IN.)	SO. FT.	172	-	-	73	-	-	-	-	-	-	-	99	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO. YD.	0.7	-	-	-	-	0.7	-	-	-	-	-	-	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO. YD.	132.5	-	-	25.1	-	79.1	-	13.3	-	-	-	15	
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO. YD.	491.5	-	-	246.9	21.7	100.4	39.7	50.8	9.1	22.9	-	-	
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	1	-	-	1	-	-	-	-	-	-	-	-	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	35	35	-	-	-	-	-	-	-	-	-	-	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	94	82	12	-	-	-	-	-	-	-	-	-	
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	307	-	-	-	-	155	152	-	-	-	-	-	
Z0021907	SILICONE JOINT SEALER, 1 3/4"	FOOT	382	-	-	-	87	76	77	-	-	-	142	-	
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	167	-	-	-	-	-	-	167	-	-	-	-	
Z0021914	SILICONE JOINT SEALER, 2 3/4"	FOOT	231	-	-	-	78	79	74	-	-	-	-	-	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	-	-	-	-	-	-	-	-	-	-	2	
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	6	4	2	-	-	-	-	-	-	-	-	-	
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	6	4	2	-	-	-	-	-	-	-	-	-	
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	363.7	286	52	-	-	-	-	-	-	-	-	25.7	
Z0041895	POLYMER CONCRETE	CU. FT.	11.4	-	-	-	-	-	-	11.4	-	-	-	-	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	-	-	-	-	-	-	-	-	-	-	
Z0055400	RUMBLE STRIP	FOOT	68255	54394	13861	-	-	-	-	-	-	-	-	-	
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	6	-	-	-	1	-	-	-	-	-	-	5	
X0327303	REMOVAL OF EXISTING SIGN LIGHTING UNIT WITH NO SALVAGE	EACH	17	17	-	-	-	-	-	-	-	-	-	-	
Z0012142	BRIDGE DECK SCARIFICATION (2 1/4 INCH)	SO YD	362	-	-	-	-	-	-	-	-	-	-	362	
Z0034105	MATERIAL TRANSFER DEVICE	TON	21,984	15,856	6,129	-	-	-	-	-	-	-	-	-	

* SPECIALTY ITEM

Rev.

FILE NAME = P:\2009\ME090806_Ver-Vor-Phi\CADD\W021.US20\Shets\03-500sh-t-sht-US20.dgn
 PLOT SCALE = 1:1000 / IN.
 USER = JMB
 MILLENNIA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	TVN	REVISED	-
DRAWN	TVN	REVISED	-
CHECKED	RPD	REVISED	-
DATE	4/4/2011	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 20
EAST OF PLANK ROAD TO WELD ROAD
 SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	BWRS-2	KANE	124	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 100M46	

P:\2009\ME090806_Ver-Vor-Phi\CADD\W021.US20\Shets\03-500sh-t-sht-US20.dgn