

SUMMARY OF QUANTITIES

90% FED.
10% STATE
URBAN

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	5	5
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	217	217
25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
25100630	EROSION CONTROL BLANKET	SQ YD	217	217
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	464	464
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	94	94
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,413	2,413
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	163	163
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6
63200310	GUARDRAIL REMOVAL	FOOT	130	130
64200105	SHOULDER RUMBLE STRIPS	FOOT	5,050	5,050
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6,224	6,224
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,075	2,075
* 72000100	SIGN PANEL - TYPE 1	SQ FT	101	101
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	18	18
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	13	13
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	165	165
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,200	12,200
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	155	155
78200420	GUARDRAIL MARKERS, TYPE B	EACH	5	5
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	6	6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,745	3,745
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	155	155
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	50	50
Δ X2503100	MOWING	UNIT	20	20
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0325866	CENTER LINE - RUMBLE STRIP	FOOT	3,594	3,594

* DENOTES SPECIALTY ITEM
Δ NON-PARTICIPATING

FILE NAME =	USER NAME = _USER_	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 19 - EAST OF DES PLAINES RIVER RD TO IL 171 SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL		DRAWN - EF	REVISED -			345	2010-118-1	COOK	17	3	
	PLOT SCALE = 50.0000' / IN.	CHECKED - RS	REVISED -			CONTRACT NO. 60M55					
	PLOT DATE = 4/11/2011	DATE - 04-12-2011	REVISED -			SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	