



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 9, 2011

SUBJECT: FAP Route 846 (IL 53)
Section 4-RS-4
Will County
Contract No. 60N05
Item No. 69, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Revised page 25 of the Special Provisions.
4. Added page 92 to the Special Provisions.
5. Revised sheets 1 - 4, 6 - 9, 11 & 14 - 17 of the Plans.
6. Added sheets 14A - 14H, 15A, 16A - 16H & 25A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60N05

State Job # - C-91-222-11
 PPS NBR - 1-78238-0000
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 4-RS-4

Project Number

Route

FAP 846

* REVISE : JUNE 7, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0326767	PROF DMD GRND CON PVT	SQ YD	120.000				
X4060826	P LB MM IL-4.75 N50	TON	80.000				
X4200740	PCC OVERLAY 4	SQ YD	125,350.000				
X5539700	SS CLEANED	FOOT	1,550.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
*ADD X7030030	WET REF TEM TAPE T3 4	FOOT	101,726.000				
Z0018500	DRAINAGE STR CLEANED	EACH	8.000				
*ADD Z0024478	FLEX DELINEATORS	EACH	15.000				
Z0030850	TEMP INFO SIGNING	SQ FT	51.400				
Z0062456	TEMP PAVEMENT	SQ YD	5,701.000				
*ADD Z0070605	TEMP IMP ATT (ST OWN)	EACH	3.000				
20200100	EARTH EXCAVATION	CU YD	1,901.000				
20400800	FURNISHED EXCAVATION	CU YD	2,187.000				
21101615	TOPSOIL F & P 4	SQ YD	635.000				
21101805	COMPOST F & P 2	SQ YD	635.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60N05

State Job # - C-91-222-11
 PPS NBR - 1-78238-0000
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 4-RS-4

Project Number

Route

FAP 846

* REVISE : JUNE 7, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25000210	SEEDING CL 2A	ACRE	1.000				
25000400	NITROGEN FERT NUTR	POUND	90.000				
25000500	PHOSPHORUS FERT NUTR	POUND	90.000				
25000600	POTASSIUM FERT NUTR	POUND	90.000				
40600200	BIT MATLS PR CT	TON	1.000				
40600300	AGG PR CT	TON	4.000				
40600400	MIX CR JTS FLANGEWYS	TON	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	500.000				
40603340	HMA SC "D" N70	TON	755.000				
42101300	PROTECTIVE COAT	SQ YD	125,350.000				
44000100	PAVEMENT REM	SQ YD	5,701.000				
44000159	HMA SURF REM 2 1/2	SQ YD	1,370.000				
44000165	HMA SURF REM 4	SQ YD	125,350.000				
*ADD 44201777	CL D PATCH T2 11	SQ YD	200.000				
*ADD 44201781	CL D PATCH T3 11	SQ YD	100.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60N05

State Job # - C-91-222-11
 PPS NBR - 1-78238-0000
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 4-RS-4

Project Number

Route

FAP 846

* REVISE : JUNE 7, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD 44201783	CL D PATCH T4 11	SQ YD	500.000				
44213200	SAW CUTS	FOOT	91,640.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	33,910.000				
*ADD 70300280	TEMP PVT MK LINE 24	FOOT	800.000				
*ADD 70400100	TEMP CONC BARRIER	FOOT	2,000.000				
*ADD 78000200	THPL PVT MK LINE 4	FOOT	2,700.000				
*ADD 78000400	THPL PVT MK LINE 6	FOOT	350.000				
*ADD 78000500	THPL PVT MK LINE 8	FOOT	100.000				
*ADD 78000600	THPL PVT MK LINE 12	FOOT	400.000				
78006110	PREF THPL PM LINE 4	FOOT	101,726.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	292.000				
78008210	POLYUREA PM T1 LN 4	FOOT	102,944.000				
78008230	POLYUREA PM T1 LN 6	FOOT	1,180.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60N05

State Job # - C-91-222-11
 PPS NBR - 1-78238-0000
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - 4-RS-4

Project Number

Route

FAP 846

* REVISE : JUNE 7, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008240	POLYUREA PM T1 LN 8	FOOT	1,405.000				
78008250	POLYUREA PM T1 LN 12	FOOT	445.000				
78008270	POLYUREA PM T1 LN 24	FOOT	32.000				
* 78100100	RAISED REFL PAVT MKR	EACH	700.000				
*ADD 78100200	TEMP RAIS REF PVT MKR	EACH	2,400.000				
78300100	PAVT MARKING REMOVAL	SQ FT	50,500.000				
* 78300200	RAISED REF PVT MK REM	EACH	2,635.000				

LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATION, FOR SPEEDS ≤ 40 MPH (BDE)..... 57

LIQUIDATED DAMAGES (BDE)..... 57

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 57

PAVEMENT MARKING REMOVAL (BDE) 58

PAYMENTS TO SUBCONTRACTORS (BDE) 58

PORTLAND CEMENT CONCRETE INLAY OR OVERLAY (BDE) 59

POST MOUNTING OF SIGNS (BDE)..... 61

RAISED REFLECTIVE PAVEMENT MARKERS (BDE)..... 62

SEEDING (BDE) 62

SELECTION OF LABOR (BDE)..... 64

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 65

TEMPORARY RAISED PAVEMENT MARKER (BDE)..... 65

TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) 66

UTILITY COORDINATION AND CONFLICTS (BDE)..... 66

WORKING DAYS (BDE) 72

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID)..... 72

FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 75

PROJECT LABOR AGREEMENT 79

TYPE III TEMPORARY TAPE FOR WET CONDITIONS 92

Revised 06/09/2011

TYPE III TEMPORARY TAPE FOR WET CONDITIONS

Effective: February 1, 2007

Revised: February 1, 2011

Description. This work shall consist of furnishing, installing, and maintaining Type III Temporary Pavement Marking Tape for Wet Conditions.

Materials. Materials shall be according to the following.

Item	Article/Section
(a) Pavement Marking Tape	1095.06

Initial minimum reflectance values under dry and wet conditions shall be as specified in Article 1095.06. The marking tape shall maintain its reflective properties when submerged in water. The wet reflective properties will be verified by a visual inspection method performed by the Department. The surface of the material shall provide an average skid resistance of 45 BPN when tested according to ASTM E 303.

CONSTRUCTION REQUIREMENTS

Type III Temporary Tape for Wet Conditions shall meet the requirements of Article 703.03 and 703.05. Application shall follow manufacturer's recommendations.

Method of Measurement. This work will be measured for payment in place, in feet (meters).

Basis of Payment. This work will be paid for at the contract unit price per foot (meter) for WET REFLECTIVE TEMPORARY TAPE TYPE III of the line width specified, and at the contract unit price per square foot (square meter) for WET REFLECTIVE TEMPORARY TAPE TYPE III, LETTERS AND SYMBOLS.

Added 06/09/2011