

**SUMMARY OF QUANTITIES**

ITEM NO.	SPECIALTY ITEM	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY <i>URBAN</i> <i>100% STATE</i>	CONSTRUCTION TYPE CODE	
							BRIDGE, NEW CONSTRUCTION	
							0008	
							80% FED - 20% STATE	
1			20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
2			20200100	EARTH EXCAVATION	CU YD	448	448	
3			20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,843	4,843	
4			20400800	FURNISHED EXCAVATION	CU YD	31,374	31,374	
5			21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	1,000	1,000	
6			25000350	SEEDING, CLASS 7	ACRE	3.25	3.25	
7			25000400	NITROGEN FERTILIZER NUTRIENT	POUND	293	293	
8			25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	293	293	
9			25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	293	293	
10			25100135	MULCH, METHOD 4	ACRE	3.25	3.25	
11			28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	734	734	
12			28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9,295	9,295	
13			28000305	TEMPORARY DITCH CHECKS	FOOT	364	364	
14			28000400	PERIMETER EROSION BARRIER	FOOT	2,358	2,358	
15			28000500	INLET AND PIPE PROTECTION	EACH	6	6	
16			28001000	AGGREGATE (EROSION CONTROL)	TON	108	108	
17			28100105	STONE RIPRAP, CLASS A3	SQ YD	47	47	
18			542A3367	PIPE CULVERTS, CLASS A, TYPE 5 12"	FOOT	372	372	
19			66400105	CHAIN LINK FENCE, 4'	FOOT	675	675	
20		*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	150	150	
21		*	66900205	SPECIAL WASTE DISPOSAL	CU YD	80	80	
22			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
23			67100100	MOBILIZATION	L SUM	1	1	
24			70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20	
25			X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
26			Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	630	630	
27			Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
28			Z0019600	DUST CONTROL WATERING	UNIT	304	304	
29			Z0022800	FENCE REMOVAL	FOOT	2,457	2,457	
30			Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
31			Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
32			Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	160	160	
33			Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	3,477	3,477	

*\*Specialty Items*

FILE NAME = ...D160N06-SHT-S00-01.DGN	USER NAME = rrtterm	DESIGNED - NMR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES CANADIAN PACIFIC RAILWAY</b>		F.A.U RTE. 1321	SECTION 2010-134-T	COUNTY	TOTAL SHEETS 40	SHEET NO. 4
PLOT SCALE = 70,0000' / IN.	CHECKED - LGP	REVISED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	DUPAGE	CONTRACT NO. 60N06		
PLOT DATE = 3/25/2011	DATE - 03/17/2011	REVISED -	REVISED -				TO STA.	ILLINOIS FED. AID PROJECT			