

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES							
				0005										0005						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	275	275						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4191	4191						
25200110	SODDING, SALT TOLERANT	SO YD	275	275						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	685	685						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	41	41						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	642	642						
40600300	AGGREGATE (PRIME COAT)	TON	203	203						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	972	972						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	76	76						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	554	554						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18761	18761						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	613	613						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4191	4191						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	460	460						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	685	685						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	619	619						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	642	642						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4257	4257						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	384	384						
42001300	PROTECTIVE COAT	SO YD	733	733						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	346	346						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	825	825						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	756	756						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	50683	50683						X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2091	2091						
44000600	SIDEWALK REMOVAL	SO FT	825	825						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	328	328						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	3682	3682						X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	55	55						
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	896	896						Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2200	2200						
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SO YD	903	903						△ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	25	25						
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SO YD	1331	1331						Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4						
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1						
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4																
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																
67100100	MOBILIZATION	L SUM	1	1																
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8751	8751																
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	554	554																
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18761	18761																

△ NON-PARTICIPATING (100% STATE)  
\* SPECIALTY ITEMS