ROUTE: Mannheim (SB Waveland Ave to Belmont Ave) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	35	420	47
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	5	60	7
		SB	3	12	9	108	12
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		SB	3	12	4	48	5
		TOTALS:			697 FT		929 SY

ROUTE: Kennedy Expressway (SEB Montrose Entrance throughout the ramp) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
			ramp	16	6	96	11
			ramp	16	6	96	11
			ramp	16	6	96	11
			ramp	16	6	96	11
			ramp	16	6	96	11
			ramp	16	6	96	11
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	15	240	27
			ramp	16	8	128	14
		TOTALS:			239 FT		425 SY

ROUTE: IL 19: Irving Park Rd (Schiller Park, West of Wesley Terrace, Under the Soo Line both directions) - CRC Pavement | PATCHING = CLASS A

CROSS STREET FROM	CROSS STREET TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		EB	1	5	10	50	6
		EB	2	10	10	100	11
		EB	2	5	10	50	6
		EB	2	5	10	50	6
		EB	1	5	10	50	6
		EB	2	5	10	50	6
		EB	1	10	5	50	6
		EB	2	10	5	50	6
		WB	1	4	12	48	5
		WB	2	10	5	50	6
		TOTALS:			87 FT		61 SY

ROUTE: Kennedy Expressway (SEB Pulaski Entrance) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
			ramp	18	6	108	12
			ramp	18	6	108	12
			ramp	18	6	108	12
			ramp	18	6	108	12
			ramp	18	6	108	12
			ramp	18	15	270	30
			ramp	18	15	270	30
			ramp	9	8	72	8
			ramp	10	6	60	7
		TOTALS:			74 FT		135 SY