

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				0005															
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8															
40600300	AGGREGATE (PRIME COAT)	TON	41	41															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	62	62															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	615	615															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2248	2248															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL. 2"	SO YD	20,075	20,075															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4437	4437															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1479	1479															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	429	429															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48811	48811															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1329	1329															
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	50	50															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2366	2366															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	531	531															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2175	2175															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2175	2175															
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1538	1538															
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	643	643															

* SPECIALTY ITEM

Rev.