

SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES										
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31																		
40600300	AGGREGATE (PRIME COAT)	TON	156	156																		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	235	235																		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	2346	2346																		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8450	8450																		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	310	310																		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	78215	78215																		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																		
67100100	MOBILIZATION	L SUM	1	1																		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2																		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3020	3020																		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1007	1007																		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1580	1580																		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33224	33224																		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7374	7374																		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	6742	6742																		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3875	3875																		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1062	1062																		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1487	1487																		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1487	1487																		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2542	2542																		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1																		
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1																		
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	1979	1979																		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1																		
X8850102	INDUCTION LOOP	FOOT	100	100																		
X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO.18 4/C, TWISTED, SHIELDED	FOOT	300	300																		

* Specialty Items