ROUTE: Barrington Rd (IL 58: Golf Rd. to IL 19: Irving Park Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
	Schaumburg Road	SB	1	12	3	36	4
			2	12	3	36	4
			RTL	2	120	240	27
			1	12	6	72	8
			2	12	6	72	8
			1	12	12	144	16
			1	12	3	36	4
			2	12	3	36	4
			LTL	12	3	36	4
			1	12	18	216	24
			2	12	18	216	24
			1	12	3	36	4
			2	12	3	36	4
Schaumburg Road	Bourbon Parkway		1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	3	36	4
			2	12	3	36	4
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
	Small Drive		1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			EOP	2	40	80	9
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			EOP	2	40	80	9

ROUTE: Barrington Rd (IL 58: Golf Rd. to IL 19: Irving Park Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		SB	1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
				12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			MED	12	3	36	4
				12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			LTL	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			LTL	12	3	36	4
			1	12	8	96	11
	Bode		2	12	8	96	11
			1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			EOP	2	80	160	18
			1	12	3	36	4
			LTL	2	60	120	13
			EOP	2	100	200	22
			EOP	2	50	100	11
			1	12	3	36	4
			1	12	3	36	4
			LTL	12	3	36	4
			LTL	12	3	36	4
	Old Church Road		EOP	2	100	200	22
Old Church Road	Schaumburg Road		1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			EOP	2	100	200	22
			1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			2	12	3	36	4
			TL	2	100	200	22
			EOP	2	40	80	9
			1	12	3	36	4
			EOP	2	40	80	9
			1	12	20	240	27
			2	12	20	240	27
			1	12	3	36	4
			2	12	3	36	4

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\welchkovvv\d0260192\Design.dgn

USER NAME = WelchkovVV
PLOT SCALE = 100.0000 ' / IN.
PLOT DATE = 4/14/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
BARRINGTON RD.

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-013-RS	COOK	70	8
		CONTRACT NO. 60P02		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		