ROUTE: IL 19: Irving Park Rd. (Nagle Ave to Harlem Ave)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Narragansett	Natchez	WB	2	12	10	120	13
Natchez	Neenah	WB	2	4	40	160	18
		WB	1 & 2	2	50	100	11
		WB	2	2	25	50	6
Neenah	Nashville	WB	1	12	20	240	27
		WB	1	6	15	90	10
		WB	2	4	60	240	27
Nashville	Normandy	WB	2	4	25	100	11
		WB	2	4	10	40	4
		WB	2	6	10	60	7
		WB	1 & 2	2	15	30	3
Normandy	Oak Park	WB	2	6	50	300	33
		WB	2	6	40	240	27
		WB	2	4	25	100	11
		WB	2	6	25	150	17
Oak Park	New Castle	WB	2	6	120	720	80
		WB	2	4	75	300	33
New Castle	New England	WB	2	4	40	160	18
		WB	2	4	15	60	7
		WB	2	4	20	80	9
New England	New Land	WB	2	12	15	180	20
		WB	2	12	25	300	33
		WB	2	6	150	900	100
		WB	1	12	8	96	11
		WB	1	12	15	180	20
New Land	Sayre	WB	2	6	25	150	17
		WB	2	12	10	120	13
Sayre	Nora	WB	2	12	15	180	20
		WB	2	6	60	360	40
		WB	2	6	20	120	13
		WB	2	6	80	480	53
Nora	Nordica	WB	2	6	60	360	40
		WB	2	12	15	180	20
Nordica	Nottingham	WB	2	6	40	240	27
		WB	2	12	50	600	67
		WB	2	12	170	2040	227
Nottingham	Harlem	WB	2	4	75	300	33
		WB	1 & 2	24	10	240	27
		WB	2	4	50	200	22
		WB	2	6	20	120	13
		TOTALS:			2186 FT		1691 SY

ROUTE: IL 19: Irving Park Rd. (EB to NB Turn Lanes @ Mannheim)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Left Turn Lanes	Mannheim	EB	LT1&LT2	24	400	9600	1067
		TOTALS:			400 FT		1067 SY

ROUTE: IL 19: Irving Park Rd (No. 9526 to No. 9750)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
No. 9526	No. 9526	EB & WB	1EB & 1WB	15	15	225	25
Wagner Rd	Wagner Rd	EB	1	4	24	96	11
No. 9750	No. 9750	EB	1	12	15	180	20
		TOTALS:			54 FT		56 SY

ROUTE: IL 19: Irving Park Rd (Mannheim Rd to Taft Ave)

CROSS STREET		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Mannheim		WB	2 & 3	2	60	120	13
		WB	1 & 2	2	150	300	33
		WB	1	12	12	144	16
		WB	1 & 2	2	200	400	44
		WB	1 & 2	24	10	240	27
		WB	1	12	35	420	47
		WB	1	12	8	96	11
		WB	1 & 2	24	15	360	40
		WB	2	12	8	96	11
		WB	1 & 2	2	80	160	18
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	25	300	33
		WB	1 & 2	2	200	400	44
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1 & 2	2	50	100	11
		WB	1 & 2	2	200	400	44
		WB	1	12	8	96	11
		WB	2	12	8	96	11
	Seymour	WB	1	12	8	96	11
Seymour		WB	2	12	8	96	11
		WB	2	12	8	96	11
		WB	2	12	40	480	53
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	40	480	53
		WB	1 & 2	2	60	120	13
		WB	2	12	10	120	13
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	2	12	8	96	11
		WB	1 & 2	24	10	240	27
		WB	1	12	6	72	8
		WB	2	12	12	144	16
		WB	2	2	50	100	11
		WB	1 & 2	24	10	240	27
		WB	1 & 2	24	10	240	27
		WB	2	12	8	96	11

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260192\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/14/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 19

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-013-RS	COOK	70	19
		CONTRACT NO. 60P02		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		