ROUTE: IL 62 (0.25 mi w/o IL 53 to 0.5 mi e/o Roselle Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		WB	2	12	4	48	5
		WB	2	12	2	24	3
		WB	2	12	2	24	3
		WB	1	14	2	28	3
		WB	2	12	2	24	3
		WB	2	12	2	24	3
		WB	2	12	2	24	3
		WB	2	12	2	24	3
		WB	2	12	2	24	3
		WB	2,RT	16	2	32	4
		WB	2,RT	16	4	64	7
		WB	1	14	2	28	3
		WB	2,RT	20	2	40	4
		WB	LT,1	14	2	28	3
		WB	LT,1	16	2	32	4
		WB	RT	12	2	24	3
	Quentin Rd.	WB	2,Ret	2	100	200	22
Quentin Rd.		WB	2	4	4	16	2
		WB	2	12	4	48	5
		WB	1	12	2	24	3
		WB	2	12	2	24	3
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	1	12	2	24	3
		WB	2	12	2	24	3
		WB	2	12	4	48	5
		WB	2	12	2	24	3
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	4	4	16	2
		WB	1	14	2	28	3
		WB	2	12	2	24	3
		WB	1	14	4	56	6
		WB	2	12	4	48	5
		WB	2	4	4	16	2
		WB	1	14	2	28	3
		WB	2	12	8	96	11
		WB	1	14	2	28	3
		WB	2	12	2	24	3
		WB	2	13	2	26	3
		WB	2	12	4	48	5
		WB	2	4	8	32	4
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	4	8	32	4
		WB	2	4	6	24	3
		WB	2	13	6	78	9
		WB	1	14	4	56	6
		WB	2	12	4	48	5
		WB	2	13	4	52	6
		WB	1	14	2	28	3
		WB	1	14	4	56	6
		WB	2	12	4	48	5
		WB	2	4	4	16	2
		WB	1	14	2	28	3
		WB	2	12	2	24	3

ROUTE: IL 62 (0.25 mi w/o IL 53 to 0.5 mi e/o Roselle Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		WB	2	12	4	48	5
		WB	2	12	2	24	3
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	13	4	52	6
		WB	2	4	4	16	2
		WB	2	11	2	22	2
		WB	2	13	2	26	3
		WB	2	12	4	48	5
		WB	2	12	160	1920	213
	0.5 mi e/o Rosele Rd.	WB	1	14	2	28	3
		TOTALS:			5717 FT		4503 SY

ROUTE: IL 68 (Arlington Heights Rd to Barrington Rd)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Barrington Rd.		EB	1	12	20	240	27
		EB	1	4	4	16	2
		EB	1	12	5	60	7
		EB	1	12	2	24	3
		EB	1	12	6	72	8
		EB	1	4	4	16	2
	Stone Canyon Cir.	EB	1	12	4	48	5
Stone Canyon Cir.		EB	1	4	85	340	38
		EB	1	12	4	48	5
		EB	RT	12	4	48	5
		EB	RT	12	4	48	5
		EB	1,Ret	4	50	200	22
	Hillshire Dr.	EB	Ret	6	14	84	9
Hillshire Dr.		EB	1	12	4	48	5
		EB	1	12	2	24	3
		EB	1	12	4	48	5
		EB	1	12	2	24	3
		EB	1	12	4	48	5
		EB	1	12	2	24	3
		EB	1	12	2	24	3
		EB	1	12	4	48	5
		EB	1	12	2	24	3
		EB	1	12	2	24	3
		EB	1	12	2	24	3
		EB	1	12	4	48	5
		EB	1	12	20	240	27
		EB	1	4	6	24	3
	S. Grove Ave	EB	1	13	4	52	6
S. Grove Ave		EB	1	13	2	26	3
		EB	1	4	40	160	18
		EB	1	13	2	26	3
		EB	1	13	4	52	6

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260192\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/14/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 62 & IL 68

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-013-RS	COOK	70	35
		CONTRACT NO. 60P02		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		