ROUTE: Northwest Hwy (Harlem Ave to Milwaukee Ave)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Harlem		S-EB	2	3	20	60	7
			2	7	120	840	93
			1	2	100	200	22
			2	3	70	210	23
			1	10	10	100	11
			2	8	70	560	62
			1	16	3	48	5
			2	3	135	405	45
			1	2	20	40	4
			1	2	5	10	1
			1,2	21	6	126	14
			2	3	75	225	25
	Nevada		1	3	20	60	7
Nevada		S-EB	2	3	130	390	43
			1	5	5	25	3
			1,2	20	6	120	13
			2	5	100	500	56
			1,2	20	2	40	4
			1,2	16	6	96	11
			1,2	19	6	114	13
			2	3	80	240	27
			1	2	20	40	4
			1,2	20	2	40	4
			1,2	20	2	40	4
			1	2	60	120	13
			1	5	5	25	3
			1	5	15	75	8
			2	5	5	25	3
			2	3	125	375	42
			1,2	21	2	42	5
			1,2	21	3	63	7
			1	2	30	60	7
			1	2	20	40	4
			1	10	4	40	4
			1,2	20	5	100	11
			1,2	24	20	480	53
			1,2	24	2	48	5
			1,2	24	2	48	5
			1	2	50	100	11
			2	5	40	200	22
			1,2	19	2	38	4
			1,2	10	4	40	4
			2	3	120	360	40
			1,2	14	50	700	78
			1	3	50	150	17
			1,2	12	2	24	3
			2	90	3	270	30
			1,2	21	2	42	5
			1,2	12	3	36	4
			1	30	2	60	7
	Sayre		1	2	3	6	1
Sayre		S-EB	1,2	24	60	1440	160
			2	7	70	490	54
			1,2	17	6	102	11
			1,2	20	20	400	44
			1,2	24	6	144	16

ROUTE: Northwest Hwy (Harlem Ave to Milwaukee Ave)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
			2	3	70	210	23
			1,2	14	70	980	109
			1	7	6	42	5
			2	3	300	900	100
			1,2	14	300	4200	467
			2	7	5	35	4
			2	7	3	21	2
			2	2	3	6	1
			2	7	5	35	4
			2	7	5	35	4
	Niagra		1,2	24	55	1320	147
Niagra		S-EB	1,2	20	60	1200	133
			1,2	14	50	700	78
			1,2	16	180	2880	320
			1,2	16	80	1280	142
			1,2	16	35	560	62
			1,2	24	80	1920	213
			2	10	16	160	18
			2	10	16	160	18
	Raven		1,2	24	4	96	11
Raven		S-EB	1,2	24	50	1200	133
			1,2	18	60	1080	120
			1	8	8	64	7
			1	2	150	300	33
			2	6	3	18	2
			2	6	3	18	2
			2	10	10	100	11
			1,2	20	4	80	9
			1	2	150	300	33
			2	8	2	16	2
			1,2	20	3	60	7
			1,2	20	3	60	7
			1,2	10	55	550	61
			1,2	10	20	200	22
			1,2	12	50	600	67
	Nettleton		1,2	5	20	100	11
Nettleton		S-EB	2	2	70	140	16
			1,2	24	5	120	13
			1,2	24	6	144	16
			1,2	14	3	42	5
			1,2	14	3	42	5
			1,2	8	20	160	18
			1,2	4	40	160	18
			1	3	50	150	17
			1,2	8	50	400	44
			2	8	100	800	89
			2	3	20	60	7
			2	5	50	250	28
			1	4	30	120	13
			2	3	60	180	20
	Neola		2	3	40	120	13
Neola		S-EB	2	10	10	100	11
			1,2	15	30	450	50
			2	6	6	36	4
			1,2	24	3	72	8
			2	5	30	150	17

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\welchkovvv\d0260192\Design.dgn	USER NAME = WelchkovVV	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	DRAWN -	REVISED -
	PLOT DATE = 4/14/2011	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
NORTHWEST HWY.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-013-RS	COOK	70	47
		CONTRACT NO. 60P02		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		