

ROUTE: US 12: Rand Rd. (Lake Cook Rd to IL 83)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		N/B	1.0	12	6	72	8
		S/B	1.0	12	12	144	16
		N/B	1.0	12	5	60	7
		N/B	1.0	12	5	60	7
		S/B	1.0	12	5	60	7
		N/B	1.0	12	5	60	7
		N/B	1.0	12	5	60	7
		S/B	1.0	12	5	60	7
		N/B	1.0	12	5	60	7
		S/B	1.0	12	5	60	7
		N/B	1.0	12	6	72	8
		S/B	1.0	12	6	72	8
		N/B	1.0	12	5	60	7
		N/B	2.0	12	5	60	7
		S/B	1.0	12	5	60	7
		S/B	2.0	12	5	60	7
		N/B	1.0	12	10	120	13
		N/B	2.0	12	10	120	13
	IL - 83	S/B	1.0	12	6	72	8

TOTALS: 4536 FT 2627 SY

ROUTE: Edens Expressway (SB Deerfield Exit Long Arm)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		SB	1	3	75	225	25
		SB	1	30	3	90	10
		SB	1	30	3	90	10
		SB	1	30	3	90	10
		SB	1	30	3	90	10
		SB	1	30	4	120	13
		SB	1	30	3	90	10

TOTALS: 94 FT 89 SY

ROUTE: US 20 (e/o Shales Pkwy to w/o Naperville Rd)

CROSS STREET		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
e/o Shales		EB	1	6	4	24	3
			2	6	3	18	2
			1	12	3	36	4
			2	12	3	36	4
			1	3	15	45	5
			2	12	3	36	4
			2	12	10	120	13
			1	6	4	24	3
			1	12	3	36	4
	w/o Naperville Rd	EB	2	12	3	36	4
w/o Naperville Rd		WB	1	12	3	36	4
			2	12	3	36	4
			1	12	3	36	4
			1	12	3	36	4
			1/2	2	80	160	18
			1/2	2	40	80	9
			2	4	120	480	53
	e/o Shales	WB	2	2	20	40	4

TOTALS: 323 FT 146 SY

NOTE: 1/2, 2/3, 3/S etc. denotes joint between lanes, shoulders and turn lanes as applicable