



SECTION C-C



SECTION B-B



SECTION A-A

HMA MIXTURE REQUIREMENTS	
MIXTURE TYPE	AIR VOIDS @ NDES
PAVEMENT RESURFACING	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (IL 9.5 mm); 2"	4% @ 70 GYR
PAVEMENT FULL-DEPTH	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (IL 9.5 mm); 2"	4% @ 70 GYR
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70, 9" (3 LIFTS)	4% @ 70 GYR
SHOULDER	
HOT-MIX ASPHALT SHOULDERS, (HOT-MIX ASPHALT BINDER IL-19 mm)	2% @ 30 GYR
PATCHING	
CLASS D PATCHES, (HMA BINDER IL-19 mm)	4% @ 70 GYR
NOTE:	
THE CONTRACTOR SHALL MILL FIRST BEFORE PATCHING	

THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX ASPHALT SURFACE MIXTURE QUANTITIES IS 112 LBS/SQYD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG 70 -22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG 64 -22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR "PERCENT OF RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.