

SUMMARY OF QUANTITIES

MRB

80% FED.
20% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0005 RESURFACING
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11
40600300	AGGREGATE (PRIME COAT)	TON	57	57
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	21	21
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	144	144
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	19	19
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,199	1,199
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	14,280	14,280
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	114	114
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	100	100
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	426	426
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,191	2,191
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	528	528
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21,910	21,910
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,064	1,064
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	320	320
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	730	730
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	264	264
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10,955	10,955
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	532	532
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	134	134
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160	160
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	90	90
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	90	90
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	62	62
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	800	800
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	206	206

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = _USER_	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	WEST LAKE AVENUE AND GREENWOOD ROAD SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILEL#		DRAWN - EF	REVISED -			•	2011-017-RS	COOK	16	3	
	PLOT SCALE = 50.0000 "/ IN.	CHECKED - RS	REVISED -			• 1284 & 2743		CONTRACT NO. 60P10			
	PLOT DATE = 4/4/2011	DATE - 04-04-2011	REVISED -			SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT