

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - HVAC - COOK COUNTY / CITY OF CHICAGO

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT		MECHANICAL 100% STATE	ELECTRICAL 100% STATE
X0327250	Unit Heater, 3KW	Each	2	2	
X0327251	Unit Heater, 3.3KW	Each	14	14	
X0327252	Split-System Air-Conditioner, 15 MBH	Each	4	4	
X0327253	Split-System Air-Conditioner, 24 MBH	Each	1	1	
X0327254	Split-System Air-Conditioner, 30 MBH	Each	3	3	
X0327255	HVAC Demolition (Mechanical and Electrical)	L Sum	1	1	
X0327242	Panelboards and Panel Mounted Circuit Breakers	L Sum	1		1
X0326599	Transformer 480-208/120V, 45KVA	Each	1		1
X8570100	Disconnect Switch	Each	8		8
X0327243	Conduit Attached to Structure, 1 1/2" Dia., Electrical Metallic Tubing	Foot	10		10
X0327244	Conduit Attached to Structure, 2" Dia., Electrical Metallic Tubing	Foot	60		60
X0327245	Conduit Attached to Structure, 3/4" Dia., Electrical Metallic Tubing	Foot	1240		1240
X0327246	Cable Assembly in Conduit, 2 NO. 12 AWG THHN, NO. 12 Ground	Foot	1240		1240
X0327247	Cable Assembly in Conduit, 3 NO. 4 AWG THHN, NO. 8 Ground	Foot	10		10
X0327248	Cable Assembly in Conduit, 4 NO. 2 AWG THHN, NO. 6 Ground	Foot	30		30
X0327249	Cable Assembly in Conduit, 4 NO. 2/0 AWG THHN, NO. 6 Ground	Foot	30		30

T:\16843A-CongressParkwayBridge\Drawings\016244E-60P18-FSR-063ME3.dgn  
3/25/2011 6:51:54 PM

**PB Americas, Inc.**  
 230 WEST MONROE STREET,  
 SUITE 900  
 CHICAGO, IL 60606  
 (312)782-8150

USER NAME: kjenstra	DESIGNED: S. KALYONCU	REVISIONS:
PLOT SCALE:	CHECKED: K. TELLA	REVISIONS:
PLOT DATE: 3/25/2011	DRAWN: E. KIENSTRA	REVISIONS:
	CHECKED: K. TELLA	REVISIONS:

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
FOR STRUCTURE NO. 016-2445**

SHEET NO. ME3 OF ME3 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
389	2424.2B-I-2	COOK	14	4
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P18	