

SUMMARY OF QUANTITIES					PAVEMENT	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					0005	
	20101700	SUPPLEMENTAL WATERING	UNIT	3	3	
	25200110	SODDING, SALT TOLERANT	SQ YD	367	367	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3529	3529	
	40600300	AGGREGATE (PRIME COAT)	TON	35	35	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	818	818	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1526	1526	
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	18	18	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2262	2262	
	42400800	DETECTABLE WARNINGS	SQ FT	488	488	
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL 2-1/4"	SQ YD	16828	16828	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	98	98	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1798	1798	
	44000600	SIDEWALK REMOVAL	SQ FT	2262	2262	
	44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	8	8	
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	230	230	
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	155	155	
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	80	80	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	48	48	
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
	60255500	MANHOLES TO BE ADJUSTED	EACH	3	3	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1798	1798	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	423	423	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1144	1144	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1496	1496	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	498	498	
	88600600	DETECTOR LOOP REPLACEMENT	FOOT	165	165	
	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1018	1018	
	Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	80	80	
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	85	85	
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	28	28	

**GENERAL NOTES**

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ECT. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 10194-QUAN-01 - IDOT P01

USER NAME =

DESIGNED -- JH

REVISED --

CHECKED -- PKB

REVISED --

PLOT SCALE =

DRAWN -- PS

REVISED --

PLOT DATE = 03-18-11

CHECKED -- AG

REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

FAU 1707 (78TH AVENUE) RESURFACING  
87TH STREET (FAU 1558) TO 79TH STREET (FAU 1548)  
SUMMARY OF QUANTITIES AND GENERAL NOTES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1707	11-00065-00-RS	COOK	16	2
CONTRACT NO. 63573				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-8003(783)				

SCALE: NA SHEET NO. 2 OF 16 SHEETS STA. TO STA.