ITEM NO.	IDOT PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITIES	STP FUNDS 70 % FED / 30 % LOCAL 0005
1	20200100	EARTH EXCAVATION	CU YD	1415	1415
2	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	195	195
3	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	627	627
4	25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2
5	31101200	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	2110	2110
6	35401100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING (VARIABLE DEPTH)	SQ YD	45	45
7	35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	899	899
8	35501336	HOT-MIX ASPHALT BASE COURSE, 13"	SQ YD	784	784
9	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40589	40589
10	40600300	AGGREGATE (PRIME COAT)	TON	232	232
11	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11	11
12	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	6597	6597
13	40600895	CONSTRUCTING TEST STRIP	EACH	2	2
14	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	864	864
15	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1680	1680
16	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9235	9235
17	42001300	PROTECTIVE COAT	SQ YD	315	315
18	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	1138	1138
19	42400800	DETECTABLE WARNINGS	SQ FT	326	326
20	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	19999	19999
21	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	94238	94238
22	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2216	2216
23	44000600	SIDEWALK REMOVAL	SQ FT	1138	1138
24	44003100	MEDIAN REMOVAL	SQ FT	208	208
25	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	75	75
26	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	560	560
27	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	55	55
28	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	100	100
29	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	1440	1440
30	44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	50	50
31	44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	50	50
32	44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	100	100
33	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	38850	38850
34	60107700	PIPE UNDERDRAINS, 6"	FOOT	360	360

ITEM NO.	IDOT PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITIES	STP FUNDS 70 % FED / 30 % LOCAL 0005
35	60603800	COMBINATION CONCRETE CURB AND GUTTER, TY B-6.12	FOOT	2166	2166
36	60605000	COMBINATION CONCRETE CURB AND GUTTER, TY B-6.24	FOOT	40	40
37	60619600	CONCRETE MEDIAN TYPE SB-6.12	SQ FT	208	208
38	67100100	MOBILIZATION	L SUM	1	1
39	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
40	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
41	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
42	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
43	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
44	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3381	3381
45	70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	905	905
46	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	61972	61972
47	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6341	6341
48	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	921	921
49	70300280	TEMPORARY PAVEMENT MARKING LINE - 24"	FOOT	472	472
50	78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	905	905
51	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	61972	61972
52	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6341	6341
53	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	921	921
54	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	473	473
55	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50
56	X8140115	HANDHOLE TO BE ADJUSTED	EACH	2	2
57	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1415	1415
58	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	9	9
59	X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	611	611
60	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
61	Z0037320	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	50	50
62	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	195	195
63	Z0076600	TRAINEES	HOUR	500	500
64	XX008130	DRAINAGE STRUCTURES TO BE CLEANED AND GROUTED	EACH	10	10

△ SPECIALTY ITEMS

⊗ CONSTRUCTION TYPE CODE= 0042

ESI CONSULTANTS, LTD
1979 N. MILL STREET, SUITE 100
NAPERVILLE, IL 60563
(630) 420-1700
WWW.ESICONSULTANTSLTD.COM
ILLINOIS DEPARTMENT OF PROFESSIONAL REGULATION REGISTRATION #184-003685

DESIGNED	MR	REVISED	-
DRAWN	DN	REVISED	-
CHECKED	MR	REVISED	-
DATE	-	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	10-00288-02-RS	DUPAGE	29	2
		CONTRACT NO. 63575		
		ILLINOIS FED. AID PROJECT		