

SUMMARY OF QUANTITIES

DATE	BY	DESIGNED	CHECKED
		PLANNED	ALIGNED
		NOTE BOOK	FILE NAME
		NO.	

DATE	BY	DESIGNED	CHECKED
		PLANNED	ALIGNED
		NOTE BOOK	FILE NAME
		NO.	

SPECIALTY ITEM	PAY ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE 0014
	28000400	PERIMETER EROSION BARRIER	FOOT	316	316
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	50	50
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3	3
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	48	48
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	21	21
	42001300	PROTECTIVE COAT	SQ YD	1,020	1,020
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	64	64
	44000100	PAVEMENT REMOVAL	SQ YD	384	384
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	198	198
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	236	236
	50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
	50102400	CONCRETE REMOVAL	CU YD	9.4	9.4
	50300225	CONCRETE STRUCTURES	CU YD	32.9	32.9
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	139.1	139.1
	50300260	BRIDGE DECK GROOVING	SQ YD	997	997
	50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	6,076	6,076
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	52,110	52,110
	50800515	BAR SPLICERS	EACH	344	344
*	50901050	STEEL RAILING, TYPE SM	FOOT	218	218
	51500100	NAME PLATES	EACH	2	2
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	112	112
	58700300	CONCRETE SEALER	SQ FT	835	835
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2

SPECIALTY ITEM	PAY ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE 0014	CONSTRUCTION TYPE CODE 0042
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	236	236	
*	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
	63200310	GUARDRAIL REMOVAL	FOOT	180	180	
	67100100	MOBILIZATION	L SUM	1	1	
	70100400	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431	EACH	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL. MO.	3	3	
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	27,736	27,736	
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300	
	70400200	RELOCATE TEMPORARY CONCRTE BARRIER	FOOT	300	300	
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	8,890	8,890	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,934	2,934	
	X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	676	676	
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	60	60	
	Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	45	45	
	Z0076600	TRAINEES	HOUR	500		500



100 S. WACKER DR.,
SUITE 500
CHICAGO, IL 60606
TEL (312) 939-1000
FAX (312) 939-4198

USER NAME = *USER*
PLOT SCALE = *SCALE*
PLOT DATE = *DATE*

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

VILLAGE OF BOLINGBROOK
WEBER ROAD OVER THE EAST BRANCH
OF THE DUPAGE RIVER

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 26 SHEETS STA. TO STA.

F.A.P.
RTE.
0856

SECTION

08-00050-00-BR

COUNTY

WILL

TOTAL
SHEETS

26

SHEET
NO.

3

CONTRACT NO. 63576

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT