

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE RESURFACING 005 80% FEDERAL 20% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	170	170
25200100	SODDING	SQ YD	120	120
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1830	1830
40600300	AGGREGATE (PRIME COAT)	TON	40	40
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	100	100
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1050	1050
42101300	PROTECTIVE COAT	SQ YD	160	160
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	20	20
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	180	180
42400800	DETECTABLE WARNINGS	SQ FT	40	40
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	9120	9120
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	500	500
44000600	SIDEWALK REMOVAL	SQ FT	550	550
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	100	100
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	200	200
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	500	500
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	700	700
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	9	9
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	500	500
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	650	650
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	720	720
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	260	260
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	525	525
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14

★ DENOTES SPECIALTY ITEM

Drawing file: K:\Projects\74010215 - 2010 LAPP Project\Quantities-TrackArea.dwg Mar 24, 2011 - 3:41pm



◆ Civil Engineers
◆ Municipal Consultants
◆ Established 1911

933 Roseville Road
Waukegan, Illinois 60154-3799
Phone: 708/665-0900
Fax: 708/665-1212

DESIGNED - --	REVISED - --
DRAWN - --	REVISED - --
CHECKED - --	REVISED - --
DATE - 01/28/11	REVISED - --

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2753	10-00092-00-RS	COOK	12	3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63577	
FED. AID PROJECT				