

SUMMARY OF QUANTITIES

PLAN REVISIONS CHECKED DATE NO.	BY DATE
---	------------

PROFILE REVISIONS CHECKED DATE NO.	BY DATE
--	------------

SPECIALTY ITEMS	PAY ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE 0011
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	32	32
	20200100	EARTH EXCAVATION	CU YD	160	160
	20300100	CHANNEL EXCAVATION	CU YD	210	210
	20800150	TRENCH BACKFILL	CU YD	58	58
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	111	111
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	2
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2
	25100630	EROSION CONTROL BLANKET	SQ YD	60	60
	25200110	SODDING, SALT TOLERANT	SQ YD	111	111
	28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	40	40
	28000400	PERIMETER EROSION BARRIER	FOOT	400	400
	28000510	INLET FILTERS	EACH	4	4
	28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	288	288
	28200200	FILTER FABRIC	SQ YD	288	288
	31101300	SUBBASE GRANULAR MATERIAL, TYPE B 5"	SQ YD	246	246
	31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	18	18
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	58	58
	40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	200	200
	42001300	PROTECTIVE COAT	SQ YD	138	138
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	36	36
	42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	SQ YD	17	17
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	826	826
	44000100	PAVEMENT REMOVAL	SQ YD	387	387
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	17	17
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	300	300
	44000600	SIDEWALK REMOVAL	SQ FT	885	885
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
	50200100	STRUCTURE EXCAVATION	CU YD	88	88
	50200300	COFFERDAM EXCAVATION	CU YD	40	40
	50202901	COFFERDAM (LOCATION - 1)	EACH	1	1
	50202902	COFFERDAM (LOCATION - 2)	EACH	1	1
	50300225	CONCRETE STRUCTURES	CU YD	66.4	66
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	97.5	98
	50300260	BRIDGE DECK GROOVING	SQ YD	331	331
	50300300	PROTECTIVE COAT	SQ YD	441	441

SPECIALTY ITEMS	PAY ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE 0011
	50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2,000	2,000
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31,730	31,730
	50800515	BAR SPICERS	EACH	54	54
	51200956	FURNISHING METAL SHELL PILES 12" X 0.179"	FOOT	1,092	1,092
	51202305	DRIVING PILES	FOOT	1,092	1,092
	51203200	TEST PILE METAL SHELLS	EACH	2	2
	51204650	PILE SHOES	EACH	28	28
	51500100	NAME PLATES	EACH	2	2
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1
	54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	1	1
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	46	46
	55100500	STORM SEWER REMOVAL 12"	FOOT	63	63
	55101900	STORM SEWER REMOVAL 48"	FOOT	15	15
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	56	56
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3
	60207115	CATCH BASINS, TYPE C, TYPE 3V FRAME AND GRATE	EACH	2	2
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1FRAME, CLOSED LID	EACH	1	1
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1
	60603800	COMBINATION CONCRETE CURB AND GUTTER,TYPE B-6.12	FOOT	264	264
	60500040	REMOVING MANHOLES	EACH	1	1
	60500050	REMOVING CATCH BASINS	EACH	1	1
	66400205	CHAIN LINK FENCE, 5'	FOOT	33	33
	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL. MO.	2	2
	67100100	MOBILIZATION	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
	XX002082	SANITARY SEWER REMOVAL 24"	FOOT	20	20
	XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	1
*	X0325670	CONCRETE BRIDGE RAIL, SIDEWALK MOUNTED	FOOT	100	100
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	75	75
	X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	222	222
	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	2	2
	X6640300	CHAIN LINK FENCE REMOVAL	FOOT	79	79
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	130	130
	Z0056626	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	9	9
	Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	15	15

URS 100 S.WACKER DR. SUITE 500 CHICAGO, IL 60606 TEL (312) 939-1000 FAX (312) 939-4198	USER NAME = #USER#	DESIGNED -	REVISED -	VILLAGE OF DEERFIELD CENTRAL AVENUE OVER THE WEST FORK, NORTH BRANCH OF THE CHICAGO RIVER	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			09-00085-00-BR	LAKE	22	3	
	PLOT DATE = #DATE#	DATE -	REVISED -			CONTRACT NO. 63584	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
	SCALE:	SHEET NO. 3 OF 22 SHEETS				STA.	TO STA.			