

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP/30% LA	0005 ROADWAY 100% LA
* CODE NO	PAY ITEM	UNIT	QUANTITY		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14	14	
20101100	TREE TRUNK PROTECTION	EACH	9	9	
20101200	TREE ROOT PRUNING	EACH	9	9	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7	7	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	2	2	
20200100	EARTH EXCAVATION	CU YD	271	271	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	220	220	
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,600	1600	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	20	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20	20	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	20	
25200110	SODDING, SALT TOLERANT	SQ YD	1,600	1600	
25200200	SUPPLEMENTAL WATERING	UNIT	6	6	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2,451	2,451	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,277	5,277	
40600300	AGGREGATE (PRIME COAT)	TON	106	106	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5	
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	1,497	1,497	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	256	256	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	127	127	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,995	2,995	
42001300	PROTECTIVE COAT	SQ YD	2,270	2,270	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	117	117	
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SQ YD	80	80	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14,840	14,840	
42400800	DETECTABLE WARNINGS	SQ FT	637	637	
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	3,845	3,845	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	197	197	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,010	2,010	
44000600	SIDEWALK REMOVAL	SQ FT	5,980	5,980	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	69	69	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	660	660	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	660	660	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	660	660	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	660	660	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60236825	INLETS, TYPE A, TYPE IIV FRAME AND GRATE	EACH	4	4	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	10	10	
60404805	FRAMES AND GRATES, TYPE IIV	EACH	3	3	
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	14	14	
60500040	REMOVING MANHOLES	EACH	1	1	
60500060	REMOVING INLETS	EACH	4	4	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,010	2,010	
67100100	MOBILIZATION	L SUM	1	1	
* 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP/30% LA	0005 ROADWAY 100% LA
* CODE NO	PAY ITEM	UNIT	QUANTITY		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	405	405	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	218	218	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6,020	6,020	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,409	1,409	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	434	434	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	191	191	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	156	156	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	209	209	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	33	33	
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	232	232	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3,010	3,010	
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	735	735	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	217	217	
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	246	246	
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	296	296	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	170	170	
K0026830	SHRUB REMOVAL	EACH	3	3	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	17,856	17,856	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	29	29	
* X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	5	5	
* X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	151	151	
* X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	35	35	
* X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	11	11	
* X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 INCH	FOOT	9	9	
* X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	232		232
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	3,010		3,010
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	735		735
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	217		217
* X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	246		246
XX000445	SAWCUT AND SEAL NEW JOINTS	FOOT	8,792		8,792
* XX006820	SIDEWALK APPROACH GUARDRAIL ADJUSTMENT	FOOT	1,015	1,015	
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	24	24	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	95	95	
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	251	251	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	220	220	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0076600	TRAINEES	HOOR	500	500	

● CONSTRUCTION TYPE CODE=0042

* SPECIALTY ITEM

FILE NAME = g:\cd\p\0056\road\plans\0-103-Quantities.dwg

USER NAME = a.pondexter
 PLOT SCALE =
 PLOT DATE = 03/25/11

DESIGNED - KB
 DRAWN - AJP
 CHECKED - ESN
 DATE - 3/28/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

WEST AVENUE
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. R.T.C.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2659	11-00177-06-RS	DUPAGE	21	3
CONTRACT NO. 63585				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				