



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME = W:\diststd\22x34\to22.dgn	USER NAME = geglierobt	DESIGNED - DRAWN -	REVISED - REVISED -
		DESIGNED - DRAWN -	REVISED - REVISED -
PLOT SCALE = 50.000 / IN.	CHECKED -	DESIGNED - DRAWN -	REVISED - REVISED -
PLOT DATE = 1/4/2008	DATE -	DESIGNED - DRAWN -	REVISED - REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ARTERIAL ROAD
INFORMATION SIGN

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE. 2659	SECTION 11-00177-00-RS	COUNTY DUPAGE	TOTAL SHEETS 21	SHEET NO. 19
TC-22		CONTRACT NO. 63585		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				