

INDEX OF SHEETS

- 1 TITLE SHEET
- 2 INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
- 3 SUMMARY AND SCHEDULE OF QUANTITIES
- 4 TYPICAL SECTIONS
- 5 SIDEWALK AND SIGNAGE PLAN
- 6 DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)

STATE STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 606001-04 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
- 701801-04 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 720001-01 SIGN PANEL MOUNTING DETAILS
- 720006-02 SIGN PANEL ERECTION DETAILS
- 729001-01 APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

GENERAL NOTES

1. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO HAVE THE UTILITY COMPANIES FIELD-LOCATE ALL UTILITIES, ASCERTAIN THEIR STATUS AND ADJUST OR RELOCATE THESE UTILITIES, AS NECESSARY, PRIOR TO STARTING CONSTRUCTION. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL NOTIFY ALL PUBLIC AND PRIVATE UTILITIES BEFORE STARTING CONSTRUCTION, INCLUDING, BUT NOT LIMITED TO:
 - A. NORTH SHORE GAS COMPANY
3001 GRAND AVENUE
WAUKEGAN, IL 60085
CONTACT: STEVE WARMINGTON
(847)-263-4666
(800)-228-6734 (EMERG.)
 - B. COMMONWEALTH EDISON COMPANY
1500 FRANKLIN BOULEVARD
LIBERTYVILLE, IL 60048
CONTACT: TERRI BLECK
(847)-816-5239
(800)-334-7661 (EMERG.)
 - C. AT&T
255 E. CHICAGO ST, FL 2
ELGIN, IL 60120
CONTACT: SHARON TILJAK
(708)709-2523
 - D. TDS METROCOM
20875 CROSSROADS CIRCLE, SUITE 800
WAUKESHA, WI 53186
MICHAEL JOHNSON
(262)754-3052
 - E. COMCAST CABLE COMPANY
688 N. INDUSTRIAL DRIVE
ELMHURST, IL 60126
MARTHA GIERAS
(630) 600-6352
 - F. CITY OF NORTH CHICAGO
1850 LEWIS AVENUE
NORTH CHICAGO, IL 60064
ATTN: JOSH WHEELER
(847)-596-8881
2. DURING THE CONSTRUCTION OPERATION WHEN ANY LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS, OR DRAINAGE STRUCTURES SO THE NATURAL FLOW OF WATER IS OBSTRUCTED, THE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS ALL DRAINAGE STRUCTURES SHALL BE FREE FROM ALL DIRT AND DEBRIS. THIS WORK SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN EXISTING FIELD CONDITIONS PRIOR TO BIDDING ON THIS PROJECT. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR FAILURE TO VERIFY EXISTING DIMENSIONS OR CONDITIONS.
4. THE CONTRACTOR SHALL LIMIT HIS CONSTRUCTION ACTIVITIES TO THE WORK AREAS DESIGNATED ON THE PLANS AND TYPICAL SECTIONS. ANY DAMAGE TO AREAS OUTSIDE OF THESE LIMITS SHALL BE REPAIRED BY THE CONTRACTOR AT HIS OWN EXPENSE TO THE SATISFACTION OF THE ENGINEER.
5. THE PROPOSED COMBINATION CONCRETE CURB AND GUTTER SHALL BE DEPRESSED AT HANDICAPPED RAMPS AND/OR AS SPECIFIED BY THE ENGINEER.
6. PROPER DRAINAGE SHALL BE MAINTAINED IN THE IMPROVEMENT AREA DURING CONSTRUCTION. THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
7. THE CONTRACTOR SHALL OBTAIN AUTHORIZATION FROM THE ENGINEER BEFORE BEGINNING WORK ON ANY STREET.
8. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROTECT ALL PAVEMENT OPENINGS, OPEN HOLES, EQUIPMENT AND RUBBLE LEFT IN THE PUBLIC RIGHT-OF-WAY. THE CONTRACTOR SHALL MAINTAIN HIGH VISIBILITY OF ALL TEMPORARY HAZARDS TO PEDESTRIANS AND MOTORISTS.
9. ALL REQUIRED SAW CUTS SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE PRICE OF THE RESPECTIVE PAY ITEM.
10. GENERAL LOCATIONS OF MOST CURB AND GUTTER, AND SIDEWALK REMOVAL HAVE BEEN SHOWN ON THE PLANS. HOWEVER, ADDITIONAL AREAS REQUIRING REMOVAL AND REPLACEMENT MAY BE DETERMINED BY THE ENGINEER IN THE FIELD. THE CONTRACT QUANTITIES HAVE BEEN ADJUSTED TO INCLUDE ALLOWANCES FOR WORK DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION.
11. ALL PARKWAYS DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE PROPERLY GRADED AND RECEIVE FOUR INCHES OF TOPSOIL AND SEEDING. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
12. ALL TREES SHALL BE PROTECTED AND CARED FOR DURING CONSTRUCTION. DAMAGES AT THE RATE OF TWO HUNDRED DOLLARS (\$200.00) PER INCH OF TRUNK DIAMETER SHALL BE CHARGED AGAINST THE CONTRACTOR FOR UNAUTHORIZED REMOVAL OR DESTRUCTION OF ANY TREE.
13. THE CONTRACTOR SHALL MAINTAIN ACCESS TO PRIVATE PROPERTIES FOR SCHOOL BUSES AT ALL TIMES.
14. AN ESTIMATED QUANTITY OF 10 CY OF FURNISHED EXCAVATION HAS BEEN INCLUDED. FURNISHED EXCAVATION SHALL BE PLACED, AS DIRECTED BY THE ENGINEER, BENEATH THE PROPOSED SIDEWALK ON THE WEST SIDE OF NATOMA AVENUE, JUST SOUTH OF 19TH PLACE.

FILE NAME = n:\p\p\5208\Design\MainSheets\5208-CenNotes01.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = espino	DESIGNED - CLG	REVISED - 8/02/2010
PLOT SCALE = 20.0000' / IN.	DRAWN - EPS	REVISED -
PLOT DATE = 4/4/2011	CHECKED - MBT	REVISED -
	DATE - 01/28/2011	REVISED -

**2011 NORTH CHICAGO
SAFE ROUTES TO SCHOOL**

INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00171-00-SP	LAKE	6	2
CONTRACT NO. 63591			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	