

CODE #	DESCRIPTION	UNIT	TOTAL 0021	Sheridan at MLK Jr. Dr.	Sheridan at 18th	Sheridan at 16th	Sheridan at 14th	Sheridan at 10th	Genesee at South	Genesee at Amstutz	Genesee at Belvidere	Belvidere at Sheridan	Interconnect
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,885		45	90							1,750
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23		1	1							21
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23		1	1							21
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23		1	1							21
25200100	SODDING	SQ YD	1,885		45	90							1,750
25200200	SUPPLEMENTAL WATERING	UNIT	122		6	3							113
* 35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	50										50
* 40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	14										14
* 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6										6
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50										50
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,215		935	1,330							950
* 42400800	DETECTABLE WARNINGS	SQ FT	152		48	64							40
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50										50
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	317		152	165							
* 44000600	SIDEWALK REMOVAL	SQ FT	3,515		1,235	1,330							950
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	317		152	165							
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2000										2000
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1										1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10										10
67100100	MOBILIZATION	L SUM	1										1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1										1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1										1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1										1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1										1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1										1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1										1
72000100	SIGN PANEL - TYPE 1	SQ FT	51		21	30							
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	155		100	55							
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2		1	1							
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	4,470										4,470
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	80		30	50							
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	95		30	65							
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	40		20	20							
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	8,150		605	615							6,930
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	75		75								
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	320		120	200							
81400100	HANDHOLE	EACH	30		4	5							21
81400300	DOUBLE HANDHOLE	EACH	2		1	1							
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	215		80	135							
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7	1			1	1	1	1	1	1	
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2		1	1							
85700500	FULL-ACTUATED CONTROLLER IN EXISTING CABINET	EACH	2				1	1					
86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	2		1	1							
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	15,000										15,000
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,500		600	900							

* = SPECIALTY ITEM

FILE NAME = N:\PROJ\5175\Design\ProposedPlan\5175-03-500.dgn

 Ciorba Group, Inc. CONSULTING ENGINEERS 5507 North Cumberland Avenue, Suite 402 Chicago, Illinois 60656 Tel. 773.775.4009 Fax 773.775.4014	USER NAME = ntumbev	DESIGNED - RJR	REVISED - Δ 6-9-2011	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SHERIDAN ROAD TRAFFIC SIGNAL IMPROVEMENTS & INTERCONNECT SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1.0000 ' / IN.	DRAWN - RJR	REVISED -			2736	09-00169-00-TL	LAKE	35	3
	PLOT DATE = 4/11/2011	CHECKED - JMV	REVISED -			CONTRACT NO. 63592				
	SCALE: SHEET NO. 3 OF 35 SHEETS STA. TO STA.					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				